

T.3 N. R.15 W.

I-8  
397  
287

W1/4 COR. SEC. 23 - Set 1" pipe.

N81W	20.20'	10" maple	PK, tag & blaze.
N27E	11.72'	10" maple	PK, tag & blaze.
N78E	19.17'	9" ash	PK, tag & blaze.
S20E	28.10'	14" maple	PK, tag & blaze.

J-7

N1/4 COR. SEC. 23 - Found iron pipe. Witnesses are from Kistler survey # 5677 of Dec. 1971.

S16W	68.35'	8" black oak	
N72E	56.42'	16" black oak	
N34E	38.35'	14" white oak	
N24W	53.36'	6" white oak	
S60W	30.51'	10" black oak	

K-8

E1/4 COR. SEC. 23 - Set 1" x 48" pipe at old fence corner.

S68W	26.20'	8" maple	PK & blaze.
N2W	3.90'	10" maple	PK & blaze.
S14E	26.10'	16" maple	PK & blaze.
N50E	16.45'	18" ash	PK & blaze.

J-9

S1/4 COR. SEC. 23 - Set 1/2" pipe.

S3W	11.44'	7" ash	PK, tag & blaze.
N28W	46.72'	10" ash	PK, tag & blaze.
N53E	28.60'	5" ash	PK, tag & blaze.

# 11

C1/8 COR., SW1/4 SEC. 23 - Set 1" pipe.

N50W	7.06'	15" ash	PK, tag & blaze.
S66E	12.17'	6" maple	PK, tag & blaze.
S27E	5.37'	10" ash	PK, tag & blaze.

# 15

S1/8 COR., SW1/4 SEC. 23 - Set 1/2" pipe.

S68W	102.83'	8" ash	PK, tag & blaze.
N81W	100.78'	5" ash	PK, tag & blaze.
N18E	70.45'	9" ash	PK, tag & blaze.

Corner is in pothole.