

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ALLEGAN

_____ (County)	Located In:	Corner Code <i>##</i>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>35</u> T <u>3N</u> R <u>15W</u>	<u>8</u>
	S <u>35</u> T <u>3N</u> R <u>15W</u>	<u>9</u>
3. Miscellaneous Property in Sec.	S <u>35</u> T <u>3N</u> R <u>15W</u>	<u>12</u>
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, GARY C. BILON, in a field survey on APRIL 15, 19 91, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(8) CORNER NOT ESTABLISHED IN ORIGINAL SURVEY. RECORDED UNDER ACT 74, P.A. 1970 BY D.A. RATEKIN 12-28-1976 AS SET 1/2" PIPE WITH CAP MIDWAY BETWEEN W1/4 POST AND CENTER OF SECTION 35. ACCESSORIES: PK NAIL N SIDE OF N. OAK 10"-14"-16" S45W 31.55', PK NAIL SOUTH SIDE 6" CHERRY N70E 67.42', PK NAIL E SIDE 12" OAK N45W 57.14'. (LCRC LIBER 3 PAGE 127)

(9) CORNER NOT SET IN ORIGINAL SURVEY. FOUND NO RECORD OF SUBSEQUENT ESTABLISHMENT.

(12) CORNER NOT ESTABLISHED IN ORIGINAL SURVEY. CORNER RECORDED UNDER ACT 74, P.A. 1970 BY D.A. RATEKIN 12-28-1976 AS SET 1/2" PIPE WITH CAP MIDWAY BETWEEN S1/4 POST AND CENTER OF SECTION 35. ACCESSORIES: PK NAIL 16" OAK E 4.92', PK NAIL 6" W. OAK N40W 10.0', PK NAIL 9" W. OAK S40W 5.37'. (LCRC LIBER 3 PAGE 127)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(8) FOUND 5/8" IRON BAR WITH CAP #8781(D.A. RATEKIN) IN ACCORD WITH THE TRIPLE OAK SW AND THE 12" OAK(NOW 14") NW. I DETERMINED THE BAR TO BE 0.33'N AND 0.04'E OF THE MIDPOINT BETWEEN I-12 AND J-12 AND ACCEPTED IT AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION OF THE CORNER.

(9) FOUND NO MONUMENTATION AT THIS POSITION. MONUMENTED CORNER WITH 1/2"x36" REBAR ENCASED IN A 4" DIAMETER CONCRETE CYLINDER CAPPED WITH A CAST ALUMINUM MICHIGAN DEPARTMENT OF NATURAL RESOURCES TABLET MIDWAY AND ON A STRAIGHT LINE BETWEEN J-12 AND K-12 AS RECORDED THIS DATE.

(12) FOUND 3/4" PIPE WITH CAP #8781 AND VERIFIED ITS POSITION MIDWAY AND ON LINE BETWEEN J-12 AND J-13 AS RECORDED THIS DATE. ACCEPTED PIPE AS THE CORNER AND REPLACED IT WITH A 1/2"x36" REBAR ENCASED IN A 4" DIAMETER CONCRETE CYLINDER CAPPED WITH A MICHIGAN DEPARTMENT OF NATURAL RESOURCES TABLET.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(8) FOUND 5/8" IRON BAR WITH CAP #8781
 S45E 47.64' SET NAIL AND MDNR TAG IN
 E. FACE 8" W. OAK
 N20E 15.59' SET NAIL AND MDNR TAG IN
 W. FACE 5" CHERRY CLUMP
 N42W 56.99' SET NAIL AND MDNR TAG IN
 E. FACE 14" W. OAK
 S60W 32.17' SET NAIL AND MDNR TAG IN
 N. FACE 15" TRIPLE OAK

(9) SET CONCRETE MONUMENT WITH MDNR CAP
 S30W 25.00' SET NAIL AND MDNR TAG IN
 W. FACE 8" AND 12" TWIN OAK
 N65E 16.81' SET NAIL AND MDNR TAG IN
 W. FACE 10" TRIPLE OAK.
 N15W 43.61' SET NAIL AND MDNR TAG IN
 W. FACE 13" W. OAK
 N70W 38.97' SET NAIL AND MDNR TAG IN
 S. FACE 11" QUADRUPLE OAK
 (BLAZED ALL TREES AT BASE AND BH)

(12) SET CONCRETE MONUMENT WITH MDNR CAP
 S50E 17.54' SET NAIL AND MDNR TAG IN
 W. FACE 8" W. OAK
 S30W 5.39' SET NAIL AND MDNR TAG IN
 S. FACE 10" W. OAK
 N40W 9.84' SET NAIL AND MDNR TAG IN
 W. FACE 6" W. OAK
 N80E 5.02' SET NAIL AND MDNR TAG IN
 S. FACE 18" B. OAK

Signed by Gary C. Bilon Date _____
 Surveyor's Michigan License No. 26453



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983