

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 3 N. R. 15 E.	1-13 1-11
2. PROPERTY CONTROLING IN SECTION	T. N. R. E.	
3. UNSETTLED PROPERTY IN SECTION	T. N. R. E.	
4. EASEMENTS	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS
 REGISTER OF DEEDS STAMP AND FILING NUMBER
 MAY 4 11 08 AM '72
 FILED

I, **DONALD A. RATEKIN** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on **SEPTEMBER 2, 1972**, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19 found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

<u>1-13</u> G.L.O. PINE 26 N 89 $\frac{1}{2}$ W 7.25	<u>1-11</u> G.L.O. PINE 18 N 31 E 32 N ^o PINE 12 S 89 W 23 N ^o
--	---

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<u>1-13</u> FOUND 1 $\frac{1}{2}$ " IRON	<u>1-11</u> FOUND STONE - 2' DEEP WITH WOOD STAKE DRIVEN ON WEST SIDE.
---	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>1-13</u> 7 $\frac{1}{2}$ " IRON E HEADWALL (SW CORNER) N40 \circ E 30.10 W HEADWALL (SE CORNER) N35 \circ W 32.75' INTERSECTION M-89 & 52ND ST. SOUTH 22.30' \pm RESET - POWER POLE N15 \circ W 56.45' 50 5310K - M-89 ROUTE MARKER SIGN N75 \circ W 50.20 49.2' OK - ST. SIGN SOUTH 45.40'	<u>1-11</u> 5 $\frac{7}{8}$ " IRON 12" OAK N42 \circ W 70.2' \checkmark YES \checkmark TRIPLE OAK, 2 @ 12" & 1 @ 6" S13 \circ W 143.9' 4' high STUMP \checkmark USGS MARKER PT STA. No. 79Y 1926 - S32 \circ W YES 28.76 18" OAK N20 \circ E 33.05' G.O.V.E
---	---

check of more 1971
OK
Cont
Cont
Reset
50 5310K
49.2' OK


SIGNED BY: Donald A. Ratekin DATE: 4-18-72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8781

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY: _____ DATE: _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY: _____ DATE: _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

Form No. ML 270
 DOUBLE DAY 6000 & 12, 6000000000

1 PAGE 270

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
 DISTRIBUTED BY MICHIGAN SOCIETY OF REGISTERED LAND SURVEYORS