

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

| FOR CORNERS OF: | LOCATED IN-: | CORNER CODE NUMBER |
|---|------------------|--------------------|
| 1. PUBLIC LAND SURVEY | T. 3 N. R. 15 E. | J-11 K-11 K-13 |
| 2. PROPERTY CONTROL- ING IN SECTION | T. N. R. E. | |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. N. R. E. | |
| 4. LOT NO. | RECORDED PLAT | |
| 5. PRIVATE CLAIMS | | |

REGISTER OF DEEDS
 MAY 4 11 09 AM '72
 FILED
 NUMBER OF DEEDS STAMP AND
 FILING NUMBER

I, DONALD A. RATEKIN do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on SEPTEMBER 6, 1971, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

| | | |
|---|---|---|
| <u>J-11</u> G.L.O. PINE 18 S 37 W 18 PINE 9 N 9 1/4 W 37 | <u>K-11</u> G.L.O. W. OAK 16 S 28 W 126 W. OAK 24 S 68 E 176 | <u>K-13</u> G.L.O. PINE 34 N 29 E 49 PINE 28 N 73 W 53 |
|---|---|---|

N 1/4 35 *NE COR 35* *SE COR 35*

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

| | | |
|---|---|---|
| <u>J-11</u> FOUND STONE. SET 1 1/2" ANGLE IRON. | <u>K-11</u> FOUND 1/2" IRON PIPE WITH 2" ANGLE IRON DRIVEN ALONG SIDE. | <u>K-13</u> 1/2" IRON ROD - 1964 FOUND 1 1/2" PIPE, PLACED ROD OVER. |
|---|---|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | | |
|--|--|---|
| <u>J-11</u> SET 1 1/2" ANGLE IRON. BLAZED 16" OAK S 10° E 79.65' BLAZED 20" OAK S 35° W 93.5' W. GATE POST N 15° W 31.4' E. GATE POST N 15° E 34.3' CL OF E & W ROAD 10' N IN LINE WITH DRIVE TO N. 66' W OF E LINE TO N | <u>K-11</u> 18" CEDAR S 65° E 158.3' 12" BLACK OAK S 25° W 43.6' 8" TWIN OAK N 85° W 24.9' 12" OAK N 60° E 118.7' - HAS SMALL BRASS BM ON ROOT 2" ANGLE IRON S 45° W 0.25' CORNER IS IN NE CORNER OF CLUMP OF WILD CHERRIES. | <u>K-13</u> IRON MON DEX TWIN 16" & 8" B. OAK SSE 69.1' 10" W. OAK SSW 75.4' 9" B. OAK NE 57.6' 4" SOUTH OF CL ROAD (M-89) 10" B. OAK NNW 69.5' |
|--|--|---|

*check by name
with JW 1991*
Reset
GONE
OK
OK
FDIP

4' high STUMP


SIGNED BY Donald A. Ratekin DATE 4-18-72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8781

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM NO. ML 736 PUBLISHED BY THE MICHIGAN SOCIETY OF REGISTERED LAND SURVEYORS
 FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
 DISTRIBUTED BY MICHIGAN SOCIETY OF REGISTERED LAND SURVEYORS

LIBER 1 PAGE 271