

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan County</u> <small>(County)</small>	Located In:	Corner Code <i>11</i>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>23</u> T <u>3N</u> R <u>15W</u>	<u>10, 11, 15</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gary C. Bilow, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(10) Established Feb. 1977 by Michigan Department of Natural Resources Surveyor Donald L. Bissell, RLS 18655 at midpoint and on line between I-8 and I-9.

(11) Established Feb. 1977 by Michigan Department of Natural Resources Surveyor Donald L. Bissell, RLS 18655, at the intersection of straight lines connecting (8) with (15) and (10) with (12), (8) and (12) being computed positions based on standard BLM instructions for subdivision of regular sections.

(15) Established Feb. 1977 by Michigan Department of Natural Resources Surveyor Donald L. Bissell at midpoint and on line between I-9 and J-9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(10) Set 1" pipe with plastic cap # 18655
 N38°E 22.24' 8" Ash PK, tag & blaze
 S40°E 14.31' 4" Willow PK, tag & blaze
 S54°W 13.93' 8" Willow PK, tag & blaze

(11) Set 1" pipe with plastic cap # 18655
 N50°W 7.06' 15" Ash PK, tag & blaze
 S66°E 12.17' 6" Maple PK, tag & blaze
 S27°W 5.37' 10" Ash PK, tag & blaze

(15) Set 1/2" pipe with plastic cap # 18655
 S68°W 102.83' 8" Ash PK, tag & blaze
 N81°W 100.78' 5" Ash PK, tag & blaze
 N18°E 70.45' 9" Willow PK, tag & blaze

Signed by Gary C. Bilow Date 8/28/90
 Surveyor's Michigan License No. 26453

