

COPY

GOVERNMENT CORNER HISTORY

SEC. COR. COMM. TO
T.2N., R.15W. & R.16W./T.3N., R.15W. & R.16W.

A-1, A-13, M-1, M-13

G.LO (LYON)	1831	W. ON S. LINE, SEC. 31, 79.45 CHS TO RANGE LINE, 69 LKS NORTH OF TEMP. COR. SET POST CORNER TOWN 2 & 3 NORTH, RANGE 15 & 16 WEST.
		SUGAR 28 S77E 40
		BEECH 36 N23W 8
MAC DOUGALL		1900'S CALLS FOR STONE
		MAPLE 14" S.W. 30
RATEKIN	1970'S	INDICATE CORNER WITH MEASUREMENTS TO ADJACENT CORNERS, BUT NO WITNESSES
MITCHELL		SURVEYS 1977-1992
		T.C.B. S.W. 77.1'
		TELE POLE S.E. 75.7'
		T.C.B. N.W. 71.75'
VAN ORDER		FOUND 1" STEEL ROD IN MON BOX C/L
		T.C.B. N.W. 71.45'
		NAIL IN SE SIDE TP S.W. 77.49'
		NAIL IN NE SIDE PP S.E. 75.76'
		NAIL IN SE SIDE PP N.E. 109.13'