

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For Corners in <u>ALLEGAN COUNTY</u>	Located In:	Corner Code #
1. Public Land Survey SOUTH 1/4 COR. SEC. 31, T3N, R15W	T..3N R..15W T..... R..... T..... R..... T..... R.....	B-13..MANLIUS TWP.
2. Property Controlling in Section	S.....T..... R..... S.....T..... R.....
3. Miscellaneous Property in Sec.	S.....T..... R..... S.....T..... R.....
4. Lot No..... Recorded Plat.....		
5. Private Claims.....		

97 JAN 22 PM 1:25
REGISTER OF DEEDS
ALLEGAN COUNTY
FILED

Register of Deeds Stamp & File Number

I, RAYMOND MOORED, in a field survey on OCT. 1988 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO 40.00 SET 1/4 SEC. POST
HEMLOCK 10 N45 1/2W 37 / HEMLOCK 8 N63 1/2E 62

RATEKIN SHOWS COR. ON SURVEY, NO WITNESSES

MITCHELL 1988 WITNESSES ONLY
20" PINE NORTH 43.42' / 24" BIRCH N.W. 58.85
TELE POLE S.E. 60.75
N. 1/4 POST SEC. 6, CLYDE TWP. 273.70' WEST

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 11-13-96
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FOUND P.K. NAIL AT CORNER POSITION AS DELINEATED BY RATEKIN SECTION BREAKDOWN INFORMATION. POSITION AS FOUND PUTS WELL ESTABLISHED CLOSING CORNER AT B-1, T.2N., R.15W., 1.78' NORTH OF RANGE LINE. DUE TO LACK OF HISTORY ON FOUND CORNER, CORNER WAS MOVED NORTH 2.00' TO RANGE LINE ESTABLISHED BY A-13 THRU B-1 AS FOUND. HELD DISTANCE EAST OF B-1 OF 273.70' AS ESTABLISHED BY RATEKIN AND MAC DOUGAL TO MATCH OCCUPATION LINE TO NORTH, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER. APPROVED BY ALLEGAN COUNTY REMON PEER GROUP 11-12-96. SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON AND CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP

S.W. COR CHURCH	N30°E 90.84'
NAIL & TAG IN E. SIDE TELE. POLE	S60°W 102.54'
N.E. COR. HOUSE	S25°E 125.21'
NAIL & TAG IN W. SIDE 26" BIRCH	N60°W 100.52'
C/L ROAD	SOUTH 3.50'

B-1 T.2N., R.15W. WEST 273.70'
C-13 T.3N., R.15W. EAST 2844.96'
C-1 T.2N., R.15W. EAST 2367.26'



Signed by Raymond Moored Date 12/13/96
Surveyor's Michigan License No. 26463