

ALLEGAN COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in <u>ALLEGAN COUNTY</u>	Located in:	Comer Code #
1. Public Land Survey SOUTH 1/4 COR. SEC. 32, T3N, R15W	T...3N R...15W T..... R..... T..... R..... T..... R.....	.....D-13.MANLIUS
2. Property Controlling in Section	S.....T..... R..... S.....T..... R.....	.....
3. Miscellaneous Property in Sec.	S..... T..... R..... S..... T..... R.....	.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

97 JAN 22 PM 1:26  
 FILED  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY  
 Register of Deeds Stamp & File Number

I, RAYMOND MOORED, in a field survey on OCT, 1986 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													


SEE BACK OF FORM FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 12-10-96  
 COUNTY REP. *Paul L. Dan O'Neil*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 FOUND 1/2" IRON W/CAP & 1" SQUARE BAR 4.15' EAST, PER L.C.R.C. BY FORD, L.4, P.384. WEST IRON MATCHES DISTANCE TO D-1, T.2N., R.15W., AS FOUND BY MIDDLETON IN L.C.R.C. L.2, P.271. ALSO MATCHES JOG OF 231' ON ASSESSORS PLAT OF VILLAGE OF FENNVILLE AS REC. BY MAC DOUGAL IN LIBER 4 OF PLATS ON PG. 38. MONUMENTATION FROM CENTER OF SECTION (D-12) SOUTH ALONG MAPLE STREET AND STREETS E. & W. OF MAPLE STREET MATCHES EAST IRON. AFTER PEER GROUP REVIEW IT WAS DETERMINED THAT THE EAST IRON SHOULD BE MONUMENTED AS D-13, T.3N., R.15W. AND THE WEST IRON BE MONUMENTED AS A PROPERTY CONTROLLING CORNER FOR INTERSECTION OF CENTERLINES OF MAPLE ST. AND M-89. SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMON IRON AND CAP. ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER. APPROVED BY ALLEGAN COUNTY REMON PEER GROUP 12-10-96.

C. Description of monument for comer and accessories established to perpetuate locating the position of the comer:  
 SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP

-BUILDING CORNER	S45°W	54.53'
-BUILDING CORNER	S45°E	46.31'
-BUILDING CORNER	N45°E	49.58'
-BUILDING CORNER	N45°W	56.18'



Signed by *Raymond Moore* Date 12/13/96  
 Surveyor's Michigan License No. 26463

GOVERNMENT CORNER HISTORY  
SOUTH 1/4 CORNER, SECTION 32  
TOWN 3 NORTH, RANGE 15 WEST

D-13

G.L.O (LYON)		40.00 SET 1/4 SEC. POST BEECH 6      N85°E 35 ELM 8        N16°W 12	
MAC DOUGALL		COUNTY SURVEYOR NOTES, SEC 32 IRON PIN STORE        NE     46.8' BANK         SE     41.7'	
RATEKIN	1971	L.C.R.C. LIBER 1 PAGE 131 FOUND NAIL IN ASPHALT CAP SET IRON PIPE W. 3.94 NE CORNER STORE    S45°W 56.1' SE CORNER STORE    N45°W 54.5' SW CORNER STORE    N45°E 46.8' NW CORNER BANK     S45°E 49.7'	
RATEKIN	1972	SURVEY, LIBER 810, PAGE 69 SAME WITNESSES AS 1971 RATEKIN L.C.R.C.	
RATEKIN	1973	SURVEY, LIBER 839, PAGE 675 NO WITNESSES	
RATEKIN	1973	SURVEY, LIBER 841, PAGE 515 NO WITNESSES	
RATEKIN	1973	SURVEY, LIBER 845, PAGE 73 NO WITNESSES	
MIDDLETON	1974	L.C.R.C., LIBER 2, PAGE 271 FOUND 3/4" PIPE-18" DEEP 3/4" PIPE CORNER IS IN C/L E. AND W. HIGHWAY CORNER IS 1' WEST OF C/L ROAD TO NORTH SOUTHWEST CORNER WOOD FACING ON BRICK BUILD      NE 49.16' NORTHWEST CORNER BRICK BUILDING                      SE 52.17' NORTHEAST CORNER BRICK BUILDING                      SW 53.41' CORNER IS 231.1' EAST OF N 1/4 POST OF SECTION 5, T.2N., R.15W.	
SMITH & SMITH	1974	SURVEY, NO WITNESSES	
DILLINGHAM	1978	SURVEY, LIBER 941, PAGE 775 SHOWS SAME WITS AS MIDDLETON L.C.R.C. IN 1974	
FORD	1994	L.C.R.C., LIBER 4, PAGE 384 FOUND STEEL BAR WITH CAP S.W. COR. BRICK BLDG. METAL FACING                      NE 48.99' N.W. COR BRICK BUILDING                                      SE 52.17' N.E. COR BRICK BUILDING                                      SW 53.38' S.E. COR BRICK BUILDING                                      NW 51.78' N 1/4 COR SEC 5, T.2N., R.15W.                              W 231.06' 1" SQUARE BAR IN CONC. PAVEMENT                      E 4.17'	
RATEKIN		WITNESS CARD SAME WITNESSES AS MIDDLETON L.C.R.C., LIBER 2, PAGE 271	
MITCHELL		WITNESS CARD PIPE-WEST-3.94 NE COR STORE        SW            56.1' SE COR STORE        NW            54.5' SW COR STORE        NE            46.8' NW COR BANK         SE            49.7'	
HOLLAND ENG.		WITNESS CARD 3/4" PIPE SAME WITNESSES AS MIDDLETON L.C.R.C., LIBER 2, PAGE 271 ALSO SHOWS WITNESSES FOR FORD L.C.R.C., LIBER 4, PAGE 384	