

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>15W</u>	<u>E-4 (E 1/4, 8)</u> <u>Manlius Twp.</u>
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

97 JUN 22 PM 1:26  
FILED  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk L. Van Order, in a field survey on Aug. 14, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- E-4  
(1) GLO North between Sec. 8 & 9 40.00 chains  
Set 1/4 Sec. post  
Tam 18 N75°W 35  
B. Oak 18 N83°E 39  
(2) T.O. Williams survey notes dated Feb. 1889  
Comm. at E. 1/4 corner thence West 80.80 chains (5332.80')  
Fd. iron with Tam wit. Attached plat shows 40.16 chains  
(2650.56') to E-3 (continued on back of sheet)

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 10-8-96  
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-4  
Kirk L. Van Order Remon. survey Aug. 14, 1996  
Fd. REM capped pipe and witnesses as stated in (3) of Part "A"  
Determined corner set incorrectly  
Set E-4 position by setting halfway and on line between E-5 and E-3, and is accepted as a careful and faithful reestablishment of the position of the original corner.  
Measured North 2649.30' to E-3 2649.30' off road traverse.  
Measured South 2649.30' to E-5  
Measured East 5340.19' to G-4 (continued on back of sheet)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4  
Removed REM capped pipe and set standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520) at E-4 position  
Nail & Remon. tag in NW side 13" Swamp Birch AZ 61°13' 22.76'  
Nail & Remon. tag in NE side 11" Maple AZ 109°00' 28.01'  
Nail & Remon. tag in NE side 8" Ash AZ 344°17' 19.25'  
Nail & Remon. tag in NW side 8" Triple Maple AZ 15°46' 16.51'  
Begin high ground AZ 358°54' 25'+/-

Signed by [Signature]  
Surveyor's Michigan License No. 23520

Date 12-31-96



MAY 2 9 1987

Section A (continued from Page 1)

E-4

Manlius Twp., T.3N., R.15W.

(3) Ray E. Moored, Wightman-Moored survey, Job #88-018, dated Feb. 29, 1988 for A.C.R.C.

Set capped pipe at corner and states approximate corner on notes

Toe of slope	N	25'
Pk NW side Twin 12" Yellow Birch	E,NE	10.4'
Pk S side 16" Pine	E	11.75'
Pk E side 9" Maple	S,SE	19.88'
Pk S side Triple Maple	N,NW	12.52'

Computed E-3 by doubling distance from E-1 to E-2 on same line extension then computing distance from E-5 to E-3 and setting E-4 on line and halfway on line between E-5 & E-3

Section B

E-4

Measured N70-22-55E 12.235' to false corner, with a line from E-4 to G-4 having a bearing of N88-36-31E

Peer group approved Oct. 8, 1996.