

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN
 (County)

Located in:

Corner Code #

		3N	15W	E-13 MANLIUS TWP.
1. Public Land Survey	T	_____	R	_____
SEC. COR. COMMON TO	T	_____	R	_____
SEC. 32 & 33, T3N, R15W,	T	_____	R	_____
2. Property Controlling	S	_____	T	_____
in Section	S	_____	T	_____
3. Miscellaneous	S	_____	T	_____
Property in Sec.	S	_____	T	_____

97 JAN 22 PM 1:26
 REGISTERED
 ALLEGAN COUNTY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, RAYMOND MOORED, in a field survey on OCT, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	19		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF FORM FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER
 P.A. 343 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 11-26-96
 COUNTY REP. Keith L. Van Orden


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON IN MON BOX FROM CORNER HISTORY. MEASURED WEST 191.20' TO E-1, T.2N., R.15W.
 MEASURED 2636.66' TO D-13, T.3N., R.15W. ACCEPTED POSITION AS CAREFUL & FAITHFUL PERPETUATION
 OF THE ORIGINAL CORNER. SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMON IRON AND CAP.
 APPROVED BY ALLEGAN COUNTY REMON PEER GROUP 11-26-96.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.

N.E. COR. TASTEE TREET RESTAURANT	S15°E	72.64'
N.W. COR. TASTEE TREET RESTAURANT	S50°E	84.17'
NAIL & TAG IN TELE. POLE	N55°W	111.12'
NAIL & TAG IN TELE. POLE	S45°W	60.18'
E-1, T.2N., R.15W.	WEST	191.20'
E-13, T.3N., R.15W.	WEST	2636.66'



Signed by Raymond Moored
 Surveyor's Michigan License No. 26463

Date 12/13/96

LIBR 0005 PAGE 465

GOVERNMENT CORNER HISTORY

SEC. COR. COMMON TO SEC. 32 & 33
TOWN 3 NORTH, RANGE 15 WEST

E -13

G.L.O (LYON)	1827	WEST S. SIDE SEC. 33, 80.00 CHAINS SET POST COMM TO SEC 32 & 33 BEECH 8 N45°W 13 PINE 16 N52°E 28
CHICHESTER	1861	COUNTY SURVEYOR NOTES SURVEY OF SECTION 32 LARGE ROUNDISH STONE HACK AT TOP & HACK AT N. SIDE
GARDNER	1879	COUNTY SURVEYOR NOTES STONE WITH "X"
MC DOUGALL	CIRCA 1900	BLACK BOOK NOTES SEC. 33, S.W. CORNER STONE W/"X" SEC. 32, S.E. CORNER HICKORY 5 NE
SURVEYOR	CIRCA 1900	SURVEYOR'S NAME UNKNOWN DISTANCE BETWEEN S.E. COR OF 32 & N.E. COR. OF 5 IN CLYDE 295 LINKS
RATEKIN	1972	L.C.R.C. LIBER 1, PAGE 273 CL MONUMENT BOX ST. SIGN S.70°W. 52.2' P. POLE S.30°E. 56.5' 26" MAPLE S.50°W. 77.5' P. POLE N.35°W. 110.6'
SMITH & SMITH	1974	MONUMENT BOX ST. SIGN S.70°W. 52.2' POWER POLE S.30°E. 56.5' 26" MAPLE S.50°W. 77.5' POWER POLE N.35°W. 110.6'
DILLINGHAM	1978	SHOWS CORNER ON SURVEY, NO WITNESSES
VAN ORDER	1987	SURVEY. FD. 1" IRON IN MON. BOX C/L HWY. M-89 N. .40' POWER POLE N.W. 111.30' TEL. POLE S.W. 60.20' NE COR. BLDG. S.E. 84.30'
RATEKIN	SEC CARD	SEC. 32 S.E. COR. MON BOX ST. SIGN S.70°W. 52.2' P. POLE S.30°E. 56.5' 26" MAPLE S.50°W. 77.5' P. POLE N.35°W. 110.6'
RATEKIN	SEC CARD	SEC. 33 S.W. COR 1946 MSHD ANGLE IRON 40" BUTTERNUT N.43°E. 53.95' 12" MAPLE S.70°E. 50.88' LIGHT POLE SOUTH 19.85'