

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

For corners in

ALLEGAN (County)	Located in:	Corner Code #
1. Public Land Survey	T 3N R 15W	F-1
	T R	N. 1/4 Cor.
	T R	Sec. 4
	T R	Manlius Twp.
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 30 PM 12: 17
James A. Blanton
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk Van Order in a field survey on November 11, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F-1
 •Corner not set by GLO
 •J.W. Hicks survey drawing dated 11/1/1875 shows a stone at corner
 •Allegan County Road Commission section corner information card:
 Punch mark in E. end conc. culvert SE 65.64'
 Punch mark in W. end conc. culvert SW 62.51'
 Punch mark in telephone pedestal SW 74.83'
 Iron E,NE 77.65'

(Continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-1
 Fd. 1" steel rod 11 1/2" long in mon. box 0.23' South of townline and 1.16' West of midpoint between E-1 & G-1. Corner was established using improper procedures and is not utilized in this survey.
 Set F-1 at a point midway between E-1 & G-1 on a line between E-13 & F-13 of T4N, R15W.
 This position not established by original government surveyors.
 This monument is accepted as the best available evidence of the position of the corner.
 Peer Group approved 3-9-94.
 Traversed 5407.07'. (on road)

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 3-9-94
 COUNTY REP. *Kirk Van Order*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-1
 Removed 1" steel rod and monument box,
 Set standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)
 Nail & Remon. tag in NE side Power Pole AZ. 284° 187.81'
 Nail & Remon. tag in NW side Power Pole AZ. 72° 155.17'
 SE corner concrete block building AZ. 349° 234.17'
 Nail & Remon. tag in Power Pole AZ. 125° 171.48'
 Capped iron Fillmore corner East 151.61'

Signed by *Kirk Van Order* Date 12-30-94
 Surveyor's Michigan License No. 23520

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

USER 0005 PAGE 138

Section A' (continued from Page 1)

•Holland Engineering, Inc. set steel bar midway, not on line
 CL SS N,NW 21.00'
 TP SW 70.98'
 Fillmore corner East 151.69'

- K.V.O. survey 6-19-81 (81-12) shows 1" steel bar w/same ties
- K.V.O. survey 8-7-85 (85-638) shows 1 1/4" rebar in mon. box w/different ties
- K.V.O. survey 4-11-91 (91-2381) shows other ties
- W-M survey 12-09-92 (92-958) shows 1" iron in mon. box with other ties used
- No LCRC found

REPRODUCED FROM THE ORIGINAL
 RECORDS OF THE
 FEDERAL BUREAU OF INVESTIGATION
 U.S. DEPARTMENT OF JUSTICE