

REMONUMENTATION

APR 25 1995

COMMISSION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>15W</u>	F-2
	T _____ R _____	Center
	T _____ R _____	Sec. 4
	T _____ R _____	Manlius Twp.
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

1994 DEC 30 PM 12:16
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
James A. [Signature]

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5				●		3	2				
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kirk Van Order, in a field survey on March 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-2

- Corner not set by GLO
- J.W. Hicks survey drawing dated 11-1-1875 shows section breakdown
 2650.56' West of W. 1/4 corner
 2651.88' North of S. 1/4 corner
 2849.22' South of N. 1/4 corner
- No LCRC or other surveys found

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-2

- Set at the intersection of the 1/4 lines
- F-2 N01°44'57"E 2849.19' to F-1
- F-2 S01°44'57"W 2641.89' to F-3
- F-2 N89°05'27"W 2646.27' to E-2
- F-2 S89°05'27"E 2642.40' to G-2

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 3-9-94
 COUNTY REP. *[Signature]*

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Peer Group approved 3-9-94.

5491.08' on road traverse
 5288.67' off road traverse

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-2

- Set standard Allegan Co. Remon. monument (3/4" x 24" steel rod w/red cap #23520)
- Nail & Remon. tag in NW side Power Pole AZ. 12°16'20" 301.89'
- Nail & Remon. tag in N side Power Pole AZ. 95°41'40" 44.46'
- Nail & Remon. tag in W side Power Pole AZ. 173°06'26" 241.49'
- Nail & Remon. tag in NW side Power Pole AZ. 220°12'52" 314.95'
- Capped iron K.V.O. #23520 N 89°05'27" W 33.00'

Signed by *[Signature]*

Date 12-30-94

Surveyor's Michigan License No. 23520

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983