

SURVEY &  
REMONUMENTATION

APR 07 1998

SECTION

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in ALLEGAN COUNTY Located In: Corner Code #

1. Public Land Survey S1/4 COR TO SEC. 33 MAN LIUS TWP. T..3N R..15W ✓...F-13.....  
T..... R.....  
T..... R.....  
T..... R.....

2. Property Controlling In Section S.....T..... R.....  
S.....T..... R.....

3. Miscellaneous Property in Sec. S..... T..... R.....  
S..... T..... R.....

4. Lot No....., Recorded Plat.....  
5. Private Claims.....

FILED  
98 JAN 21 PM 1:26  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	N
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RAYMOND MOORED, in a field survey on SEPTEMBER 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 9-9-97  
COUNTY REP. K.V.O.

A. Description of original monument and accessories and/or subsequent restoration:  
SEE BACK OF SHEET FOR CORNER HISTORY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 1" IRON IN MON BOX PER # 6-13 ABOVE. SET 3/4" X 24" ALLEGAN COUNTY REMON IRON W/REMON CAP IN PLACE OF FOUND CORNER.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY ALLEGAN COUNTY REMON PEER GROUP ON 9-9-97  
TOTAL LINEAL FEET OF ON ROAD TRAVERSING= 0

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH .CAP IN MON. BOX.  
-NAIL & TAG IN E SIDE POWER POLE N25E 69.24'  
-NAIL & TAG IN N SIDE POWER POLE N60E 161.55'  
-NAIL & TAG IN SW SIDE POWER POLE S60E 127.60'  
-NAIL & TAG IN S SIDE POWER POLE N65W 157.78'  
-C/L M-89 HWY SOUTH 9' +/-



Signed by Raymond Moored Date 12/17/97  
Surveyor's Michigan License No. 26463

GOVERNMENT CORNER HISTORY

REF 0006 PAGE 154

SOUTH 1/4 CORNER OF SECTION 33  
TOWN 3 NORTH, RANGE 15 WEST

F-13

- PART A: 1. G.L.O. L. LYON, D.S., 1831 40.00 SET POST  
BEECH 8 N45W 13  
PINE 16 N52E 26
2. A GARDNER COUNTY SURVEYOR 4-24-1879  
SECTION 33 SURVEY  
STONE W/X FOR CORNER
3. MDOT 1946 (FROM D RATEKIN WITNESS CARD)  
BOAT SPIKE OVER STONE  
S50°W 60.81' 30" MAPLE  
S55°E 71.21' 16" OAK  
N20°E 67.83' POWER POLE
4. D. RATEKIN WITNESS CARD  
"T" IRON IN MON BOX
5. D. RATEKIN SURVEY - EARLY 1960'S  
"T" IRON IN CENTER OF MON BOX  
C/L OF ROAD 9' NORTH
6. LCRC D. MIDDLETON 2-19-74 (L.2, PG.270)  
"T" IRON IN MON BOX  
CORNER 9' N OF C/L - E - W HIGHWAY  
CORNER IS IN C/L ROAD TO NORTH  
UTILITY POLE N15°E 69.37' TO NAIL  
UTILITY POLE S10°E 72.88' TO NAIL
7. D. RATEKIN SURVEY DATED 7-6-76  
"T" IRON IN MON BOX  
SAME AS NO. 6 ABOVE
8. D. RATEKIN SURVEY DATED 4-20-77  
"T" IRON IN MON BOX  
SAME AS NO. 6 ABOVE
9. K. VAN ORDER SURVEY DATED 10-6-87  
"T" IRON IN MON BOX  
C/L HIGHWAY M-89 SOUTH 8.39'  
P. POLE N.E. 69.40'  
NORTH SIGN POST NORTHEAST 73.18'  
C/L STREET SIGN NORTHEAST 38.2'  
C/L STOP SIGN NORTHWEST 39.9'
10. WIGHTMAN - MOORED SURVEY DATED 4-12-88  
USED CORNER - NO WITNESSES.
11. MITCHELL SURVEY'S INC. SURVEY DATED 8-11-94  
"T" IRON IN MON BOX  
P. POLE N20E 69.24'  
P. POLE N60W 157.78'  
P. POLE S60E 129.60'  
P. POLE N60E 161.55'  
C/L M-89 HIGHWAY S. 9' +/-
12. MITCHELL SURVEYS INC. WITNESS SHEET 1995  
SAME AS NO. 11 ABOVE
13. HOLLAND ENGINEERING INC. WITNESS SHEET  
"T" IRON IN MON BOX  
NAIL IN UTILITY POLE N.N.E. 69.37'  
NAIL IN UTILITY POLE S.S.E. 72.88'