

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan</u> <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T <u>3</u> N R <u>15</u> W	<u>G-4 (E 1/4, 9)</u> <u>Manlius Twp.</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

97 JAN 22 PM 1:26
FILED
REGISTER OF DEEDS
ALLEGAN COUNTY
Michigan

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk L. Van Order, in a field survey on Aug. 5, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
G-4
 (1) GLO Set post 40.00 chains North of G-5
 8" White Ash S82°E 7 links
 12" Beech S54°W 26 links
 (2) T.O. Williams survey of Feb. 1889
 Measured 40.00 chains South of G-3
 Found stake with Beech wit., put in iron. 48.37 chains to river
 Above according to written notes (continued on back of sheet)


APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 8-13-96
 COUNTY REP. Kirk L. Van Order

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.
G-4
 Kirk L. Van Order Remon. work Aug. 5, 1996
 Did not find iron set by T.O. Williams in 1889
 Fd. traces of old barbed wire fence North and South of position set by midway and on line between G-3 and G-5, and is accepted as a careful and faithful reestablishment of the position of the original corner.
 G-3 North 2645.90'
 G-5 South 2645.90'
 Peer group approved Aug. 13, 1996.
 3145.90' off road traverse.
 2145.90' on road traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.
G-4
 Set standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)
 Nail & Remon. tag in S side 8" Ash S80°E 14.66'
 Nail & Remon. tag in SW side 10" Ash S30°E 18.41'
 Nail & Remon. tag in S side 11" Ash N80°W 1.31'
 Nail & Remon. tag in N side 10" Ash S75°W 9.59'
 Note: Blazed all witness trees

Signed by Kirk L. Van Order
 Surveyor's Michigan License No. 23520

Date 12-31-96



REF 0005 PAGE 471

USDA
BUREAU OF LAND MANAGEMENT

MANLIUS TWP.

Section A (continued from Page 1)

G-4

Manlius Twp., T.3N., R.15W.

- (3) MacDougall's survey drawing notes early 1900's
Iron at G-3 and measured South 40.30 chains
Var 1°-25' to found iron at G-4
- (4) MacDougall's survey drawing notes early 1900's
West 1/4 corner Section 10 shows iron
4" Elm E 6'
3" Elm S 7.5'
Rabbit River 8.37 chains South
- (5) Don Ratekin tie card for Section 10 shows computed position
midway between G-3 and G-5
2646.46' South and 2646.46' North of G-4
Also notes W. 1/4 corner - calc. pt. Holland Engineering corner
in river NW corner N 2645.76'
SW corner S 2645.76'
Center E 2673.84'
- (6) David Greer, LCRC L. 003, P. 401, May 10, 1985
Fd. no evidence of corner which is now in the river bottom -
calc. position of corner as midway and on line between G-3 and
G-5
G-3 North 2645.76'
G-5 South 2645.76'
H-4 East 2673.84'
- (7) Kirk L. Van Order survey dated July 17, 1989 shows corner not
set in river bottom. Extended East and West 1/4 line West from
East 1/4 corner thru center of Section 10.