

REMONUMENTATION

APR 25 1995

COMMISSION
For corners in

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 30 PM 12:16
REGISTER OF DEEDS
ALLEGAN COUNTY MICHIGAN
James A. Clapp

FILED

Allegan (County) Located In: Corner Code #

1. Public Land Survey T 3N R 15W G-9 NW Cor
T ___ R ___ Sec 27
T ___ R ___ Manlius Twp.
T ___ R ___

2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___

3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John P. Clapp, in a field survey on December 12, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-9 Gen. Land Office Survey Notes 1832 Calvin Britain, Surveyor Set Post 18" Pine S46°E 16 links 18" Pine N21°W 26 links	G-9 Recorded in Liber 1 Page 350, July 24, 1972 Fd 1 1/2" Pipe 10" W. Oak SE 45.35' 20" Tw. Oak S 45.72' 7" W. Oak SW 31.24'	G-9 Old County Surveyor Records show "stake" in 1906 G-9 Old County Surveyor Records show iron pipe (no date) 8" R. Oak NE 53.7' 8" W. Oak NW 61.6' 6" W. Oak SW 32' 8" W. Oak SE 46'
---	---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9
Found bolt in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner.

No ties remaining.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 12-13-94
COUNTY REP. *John P. Clapp*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9
Set A.C. Remon Iron and Cap in Monument Box
A.C. Remon Tag & Nail in SE Side 14" Twin Oak AZ. 35° 56.86'
A.C. Remon Tag & Nail in SW Side 8" Oak AZ. 144° 70.90'
A.C. Remon Tag & Nail in SE Side 15" Twin Oak AZ. 213° 66.91'
A.C. Remon Tag & Nail in NE Side 10" Pine AZ. 329° 47.38'

Signed by John P. Clapp *John P. Clapp* Date Dec. 13, 1994
Surveyor's Michigan License No. 34091

