

REMONUMENTATION

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION
For corners in

1994 DEC 30 PM 12:16
 Register of Deeds
 ALLEGAN COUNTY MICHIGAN
Robert A. Clapp

FILED

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>15W</u>	<u>G-10-W1/4-Cor</u>
	T _____ R _____	<u>Sec 27</u>
	T _____ R _____	<u>Manlius Twp.</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, John P. Clapp, in a field survey on December 12, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21							
7													
8	15	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-10 Gen. Land Office Survey Notes 1832 Calvin Britain, Surveyor Set Post 7" Pine N87°E 23 links 20" Pine S87°W 9 links	G-10 Recorded in Liber 1 Page 350, July 24, 1972 Set Concrete Monument 11" W. Oak NW 14.20' 10" W. Oak NE 10.91' 11" R. Oak S 14.48'	G-10 Old County Surveyor Records show "stake" (no date) 8" W. Oak NW 14.5' 6" W. Oak NE 11.2'
---	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10
Found concrete monument and accepted it as a careful and faithful perpetuation of the position of the original corner.
No ties remaining.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 12-13-94
COUNTY REP. Robert A. Clapp

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10 Set A.C. Remon Iron and Cap A.C. Remon Tag & Nail in WNW Side 14" Twin Oak AZ. 18°	112.92'
A.C. Remon Tag & Nail in S Side 10" Oak AZ. 108°	36.58'
A.C. Remon Tag & Nail in S Side 10" Oak AZ. 272°	52.85'
A.C. Remon Tag & Nail in ENE Side 18" Pine AZ. 342°	135.48'

Signed by John P. Clapp *John P. Clapp* Date Dec. 13, 1994
 Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, 1970
 MAY 14, 1975
 REVISED JAN., 1983

W:\Doest\Sun\Remon.doc
 FILE# 0005 PAGE 099