

**SURVEY
REMONUMENTATION**

APR 29 1999

SECTION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Allegan
(County)

Located in: _____ Corner Code # _____

1. Public Land Survey T 3N R 15W J-1
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH
Register of Deeds Stamp & File Number

LIBER 006 PAGE 88

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Steve Lampen, in a field survey on December 4, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
J-1 Gardner - 1879
GLO - Corner not Stone
Set by GLO J-1 to I-1 = 40.45 ch.
J-1 to K-1 = 40.39 ch.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
J-1 Found capped iron stamped KVO on South line of Section 35, Town 4 North, Range 15 West
J-1 to I-1 measured 2675.44 J-1 to K-1 measured 2675.14

Replaced capped iron with a 3/4"x24" Allegan County Remonumentation iron and cap. This corner not Monumented by the original GLO Survey. This position is accepted as the best available evidence of the Position of the corner.


Traversed 2634 ft. on road.

This corner was approved by the Allegan County Remonumentation Peer Group on December 8, 1998.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC. 8, 1998
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
J-1 3/4"x24" Allegan County Remonumentation iron and cap on South line Section 35, Town 4 North, Range 15 West
Azimuth - Michigan State Plane grid direction

NW corner house, brick	244° 20'	213.19
SE corner house, brick	134° 56'	170.19
SW corner house, brick	48° 24'	128.10
SW corner house, vinyl siding	313° 21'	240.62
J-13, Town 4 North, Range 15 West	91° 11'	17.08



Signed by Steven Lampen

Date JANUARY 11, 1999

Surveyor's Michigan License No. 37279