

SECTION

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Joyce A. Smith*  
REGISTER OF DEEDS  
ALLEGAN COUNTY MICH.

00 FEB - 1 AM 8:48

FILED  
1999 007 PAGES 11

For corners in

<u>Allegan</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>15W</u>	<u>M-12</u>
	T ___ R ___	<u>Manlius</u> Twp.
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk L Van Order in a field survey on Oct 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-12

- (1) GLO Original post established by U.S. Government Deputy Surveyor L. Lyon, 1832  
Pine 6 N.30W. 18, W. Oak 7 S.26W. 23
- (2) Field survey notes Co. 1937 by unknown surveyor (Book 3, Page 91)  
8" B. Oak N.62E. 75.6'  
8" Pine S.55E. 29.47'  
10" W. Oak S.18E. 90.45'

(continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12

Fd. capped 1/2" x 24" steel rorod above 1" dia. x 6" long iron pipe. Used witnesses as listed in No. 3 of Part A to find. And is accepted as a careful and faithful perpetuation of the position of the original corner. Removed capped rorod and iron pipe and replaced with a standard Allegan Co. Remon. monument.

Peer group approved Nov. 9, 1999

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED Nov. 9, 1999  
COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12

- Standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)
- Nail & Remon. tag in NW side white pine S35°W 33.90'
- Nail & Remon. tag in N side 14" white pine S90°W 31.71'
- Nail & Remon. tag in NW side 13" black oak N45°E 56.83'
- Nail & Remon. tag in NE side 21" black oak S65°E 62.62'

Signed by



Date 12-30-1999.

Surveyor's Michigan License # 23520

MAR 07 2000

SECTION

LIBR0007 MAR 3 12

Section A (continued from Page 1)

M-12

Manlius Twp., T.3N., R.15W.

- (3) DNR survey by Gary C. Bilow, April 15, 1991  
Fd. 1" iron pipe and set 1/2" rebar w/cap #26453 inside
- |   |      |        |
|---|------|--------|
| Set nail & MDNR tag in S face 7" white pine     | N62E | 34.29' |
| Set nail & MDNR tag in N face 6" white pine     | N73W | 21.14' |
| Set nail & MDNR tag in SW face 14" red pine     | N27W | 55.20' |
| Set nail & MDNR tag in S face 8" twin white oak | N82W | 12.34' |
- (4) LCRC recorded in Liber 004, Page 137 by Gary C. Bilow, dated Aug. 8, 1991  
Same witnesses as in No. 3 above