

ALLEGAN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan
COMMISSION
(County)

1. Public Land Survey	T	3N	R	16W	F-1 (N 1/4 Sec 4)
	T		R		Saugatuck Twp.
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

1993 DEC 30 PM 2:46
Jasper L. Batten
REGISTER OF DEEDS
ALLEGAN COUNTY MICHIGAN

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2												
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	20	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David R. Greer, in a field survey on December 6, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1 This corner not set by the Government
Recorded in Liber 4, Page 54, May 3, 1984
Set 1/2" iron with cap
P.K. East Side 6" Poplar NW 33.88'
P.K. SE Side 6" Pine WNW 25.05'
SE Side 2" Pine SW 52.51'
S 29 ± CL Trail
1/2" iron with cap (S 1/4 Sec 33) W 20.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1
Found cast iron monument. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.
P.K. East Side 6" Poplar NW 33.88'
P.K. SE Side 6" Pine WNW 25.05'
SE Side 2" Pine SW 52.51'
S 29 ± CL Trail
1/2" iron with cap (S 1/4 Sec 33) W 20.00'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1
Replaced 1/2" iron and cap with Allegan County Remonumentation Iron & Cap.
AZ - Michigan State Grid Direction
A.C. Remon tag & nail in N Side 6" Pine W 33.47'
P.K. East Side 6" Poplar N45°W 33.68'
P.K. SE Side 6" Pine N70°W 25.05'
P.K. SE Side 2" Pine S45°W 52.51'
Centerline Trail ± S 29.00'
F-13 S1/4 Cor T4N, R16W Remon iron w/cap W 20.00'



Signed by David R. Greer Date 12/6/93
Surveyor's Michigan License No. 16042

W:\Dec\Surv\Remon.doc