

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan (County) Located In: Corner Code #
 1. Public Land Survey T 3N R 16W G-1 (NW Sec 3)
 T R Saugatuck-Twp.
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

1993 DEC 30 PM 2:42
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
 Register of Deeds Stamp & File Number
FILED

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David R. Greer, in a field survey on December 6, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	20	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


G-1 Recorded in Liber 4, Page 54, May 3, 1989 Set 1/2" Iron with Cap CL 3" pipe end Fence Post P.K. SE Side 13" Poplar P.K. N Side 2" Pine 1/2" Iron w/cap (SW Cor Sec 34)	WNW N ESE W	69.82' 57.52' 30.63' 20.00'	G-1 Government Notes 1831 Post Pine 6" S 2 1/2 99.8 links DST No other trees near
--	----------------------	--------------------------------------	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1 Found 1/2" iron with cap and accepted it as a careful and faithful perpetuation of the position of the original corner CL 3" pipe end Fence Post P.K. SE Side 13" Poplar P.K. N Side 2" Pine 1/2" Iron w/cap (SW Cor Sec 34)	WNW N ESE W	69.82' 57.52' 30.63' 20.00'
---	----------------------	--------------------------------------

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 Replaced 1/2" Iron with Allegan County Remonumentation Iron & Cap A.C. Remon tag & nail in S Side 10" Pine Centerline 3" Pipe, S. Fence End P.K. SE Side 13" Poplar P.K. N Side 2" Pine SW Cor Sec 34, T4N R16W Remon iron w/cap	N82°W N70°W N S65°E W	79.30' 69.82' 57.75' 30.63' 20.00'
--	-----------------------------------	--



Signed by David R. Greer Date 12/14/93
 Surveyor's Michigan License No. 16042

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983