

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1995 DEC 14 PM 2:37  
REGISTERED LAND SURVEYOR  
STEVEN LAMPEN  
ALLEGAN COUNTY, MICHIGAN

FILED

For corners in  
Allegan (County) Located In: Corner Code #

1. Public Land Survey T3N R16W G-3  
T R SW cor. Sec. 3  
T R Saugatuck Twp.  
T R  
T R

2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

Register of Deeds Stamp & File Number

SURVEY &  
REMONUMENTATION

APR 29 1996

COMMISSION

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	A
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Steve Lampen, in a field survey on December 6, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-3  
Recorded in L 2-P 22 June 6, 1974  
Iron rod  
W post of guard rail NW 43.40'  
E post of guard rail NE 37.58'  
Centerline stop sign SE 60.88'  
Power and light pole SSW 27.74'  
Centerline street sign SW 29.90'

Recorded in L 4-P 6 March 13, 1987  
Nail in face of power pole SSW 27.64'  
Centerline end culvert NW 35.80'  
Centerline end culvert SW 49.30'  
10" Maple tag #14091 NW 91.60'  
10" twin Oak tag #14091 WNW 110.16'  
10" Oak tag #14091 ENE 121.36'

GLO Notes 1831  
Post  
10" B. Ash S 88°W 29 links  
18" Pine S 61°E 27 links

LCRC L 1-P 88 August 28, 1971  
Power pole S 40° W 27.78'  
Centerline S end 48" CMP S 65° W 49.30'  
Centerline N end 48" CMP N 50° W 35.79'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-3  
Found 3/4" iron and is accepted as the best available evidence of the position of the original corner  
Nail in face of power pole SSW 27.64'  
Centerline end culvert NW 35.80'  
10" Maple tag #14091 NW 91.60'  
10" twin Oak tag #14091 WNW 110.16'  
10" Oak tag #14091 ENE 121.36'


APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 3-14-95  
COUNTY REP. *[Signature]*

Power pole S 40° W 27.78'  
Centerline S end 48" CMP S 65° W 49.30'  
Centerline N end 48" CMP N 50° W 35.79'

Accepted by the Allegan County Remonumentation Committee on March 14, 1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3  
Replace 3/4" iron over iron stake with Allegan County Remonumentation iron and cap. AZ = MI State plane grid Az  
A. C. Remon. tag and nail in W side 36" Pine AZ 359° 58' 159.39'  
A. C. Remon. tag and nail in W side 12" Maple AZ 351° 19' 67.88'  
Find nail S side 12" twin Oak AZ 292° 00' 110.41'  
A. C. Remon. tag and nail in SE side power pole AZ 221° 00' 28.15'  
A. C. Remon. tag and nail in S side 8" Pine AZ 58° 36' 72.84'  
A. C. Remon. tag and nail in S side 12" Oak AZ 68° 23' 121.20'



Signed by *Steven Lampen*

Date December 14, 1993

Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
REVISED MAY 16, 1976  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993

LEF:0005 PAGE 290