

RF

NOV 6 7 2000

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
ALLEGAN COUNTY MICH.
Spencer L. Britton

00 FEB - 1 AM 8:50

FILED

LIBRARY / P-44-34

For corners in
Allegan (County) Located In: Corner Code #

1. Public Land Survey T3N R16W G-12
T R
T R E 1/4 Corner
T R Section 33
2. Property Controlling S T R Saugatuck Twp.
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

I, Steve Lampen, in a field survey on December 11, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-12
GLO - C. Britain - 1831 - Set Post
Sugar 18 S88E 23
Beech 16 S75W 13

D. Ratekin - 1973
Recorded Survey L-840, P-496
CL Road E 2.0'
NE Corner Tel Outlet N20W 104.14'
Nail N Side Power Pole N80E 69.12'
SW Corner Shed N65E 116.54'

D. Ratekin - 1973
LCRC L-2, P-235
Part "B"
Couldn't Locate Stone
Set 1" Iron at intersection of E-W
1/4 line and East line of Section
using West 1/4 post and Center and
NE Corner and SE Corner for line.
Same witnesses as L-840, P-496.

E. Mix - 1857
Stone

A. Gardner - 1880
Stone - No witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-12 Found 3/4" Iron
CL Road E 2.0'
NE Corner Tel Outlet N20W 104.14'
Nail in N Side P Pole N80E 69.12'
SW Corner Shed N65E 116.54'


Replaced 3/4" iron with an Allegan County Remonumentation iron and cap and accepted it as careful and faithful perpetuation of the position of the original corner.

Approved by the Allegan County Remonumentation Peer Group on December 14, 1999.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC. 14, 1999
COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12 Standard Allegan County Remonumentation 1/2" x 24" iron with red cap #23520.
Azimuth = Michigan State Plane grid direction.
Remonumentation tag in S side Power Pole 289° 25' 206.58'
Remonumentation tag in S side Power Pole 83° 15' 69.04'
Remonumentation tag in E side 10" Pine 167° 51' 196.86'
NW Corner House, Brick 25° 05' 337.15'
CL North-South Asphalt Road Pavement 90° 2.5'



Signed by Steven Lampen

Date DECEMBER 31, 1999

Surveyor's Michigan License No. 37279