

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan (County) Located in: Corner Code #

1. Public Land Survey T3N R16W 1-9
 T R Sec. 22, 23
 T R 26 & 27 Cor.
 T R Saugatuck Twp.

2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

1995 DEC 14 PM 2:39
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 REGISTER OF DEEDS STAMP & FILE NUMBER
 FILED

SURVEY &
 REMONUMENTATION
 APR 29 1996
 COMMISSION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gerald T. Ford, in a field survey on October 19, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1-9 Government Land Office Survey Notes, 1831 Surveyor - Lucius Lyon Post 10" Elm S 68° W 24 links 18" Beech S 45° E 40 links	Allegan Co. Survey Notes, April 1887 Surveyor - E.P. Waterman Government stake Allegan Co. Survey Notes, July 1928 Government stake & stone 8" Birch SE 29.10' 6" Elm SE 31.6'	D.A. Ratakin & Assoc. Survey Records, June 1964 Found 1 1/2" pipe 1.5' deep, placed 1" iron on top 12" Birch SE 26.3' SE 26.3' 15" Birch S 40.7' S 40.7' 16" triple Willow NW 30.9'
---	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1-9
Found 1" iron over 1 1/2" pipe
Blaze mark N side 24" Willow AZ 235° 23.1±
Iron pipe AZ 0° 33.03'
Blaze mark in N side 10" Tulip tree AZ 306° 33.5'


Replaced irons with A. C. Remon. iron and cap.

Approved by the Allegan Co. Remonumentation Peer Group on November 14, 1995 and is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 11-14-95
 COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1-9
Allegan County Remonumentation iron and cap.
 A. C. Remon. nail & tag N face twin 30" Willow AZ 262° 45.23'
 A. C. Remon. nail & tag N face (near 24" quint. Willow) AZ 235° 23.38'
 A. C. Remon. nail & tag E face 10" Tulip AZ 306° 33.49'
 A. C. Remon. nail & tag S face 10" Poplar AZ 59° 11.12'
 Iron pipe AZ 0° 33.03'



Signed by *[Signature: Gerald T. Ford]* Date November 14, 1995
 Surveyor's Michigan License No. 33976

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1976
 REVISED JAN., 1982
 ADAPTED FOR WORD PROCESSING MARCH, 1982

A. Continued

I-9

LCRC

I. 3-P 59

February 25, 1976

1" iron

P.K. nail SW side 6" river Birch in 12"-6"-3" clump	S 80° E	60.55'
P.K. nail in N side of nea 16" Willow in quint. 16" Willow	S 50° W	23.08'
P.K. nail NE side of 8" Tulip	N 60° W	33.60'
1/2" pipe	N	33.00'