

SURVEY
REMONUMENTATION

APR 29 1999

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>ALLEGAN</u> (County)	Located In: Saugatuck	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>16W</u>	<u>I-13</u>
	T <u> </u> R <u> </u>	<u>SE SEC 34</u>
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File
Number

LIBER 007 PAGE 90

I, Robert E. Lemke, in a field survey on September 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, reestablished, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
(see back of page)
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2" Iron with yellow cap no number visible
Witness's per LCRC Liber 3, page 178
(a) Measured 72.98' to center of tree (Recorded 73.60')
(b) Measured 57.40' to center of Tel. Box (Recorded 58.64')
(c) Measured 68.50' to found nail in a twin 10" Ash (Recorded 68.45' to a 8" Poplar)

Survey sketch Don Allen shows distance from S1/8 post of Sec. 34 to the SE corner of Sec. 34 = 1318.56'

H13 to I13 Measured 2637.43' (Shown as 2637.12' on Wightman Sketch Aug. 11, 1987)
I13 to I-1 Measured 7.92' to ratified corner (Shown as 8.3' +/- on Wightman Sketch Aug. 11, 1987)
And is accepted as a careful and faithful perpetuation of the position of the original corner.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" Iron with yellow cap at bituminous road surface

I-13 to I-1 West 8.22'
I-13 to H-13 2637.43'
I-13 to J-13 2643.73'
Set standard Allegan Co. Remon tag & nail in the West side of a 10" Twin Ash 3.2' above grade S 20 ° E 68.41'
Set standard Allegan Co. Remon tag & nail in the Southeast side of a 10" Cherry 3.0' above grade S 55 ° W 77.68'
Set standard Allegan Co. Remon tag & nail in the Northeast side of a 30" Maple 1.3' above grade N 55 ° W 73.45'
Set standard Allegan Co. Remon tag & nail in the East side of a power pole 2.0' above grade N 5 ° E 56.66'



APPROVED REMONUMENTATION CORNER
P.A.345 OF 1990
ALLEGAN COUNTY
DATE APPROVED NOV. 24, 1998
COUNTY REP. [Signature]

Signed by Robert E. Lemke Date 12/29/98
Surveyor's Michigan License No. 40160 for SDI Consultants

I-13 SAUGATUCK TWP.

A. Description of original monument and accessories and/or subsequent restoration: I-13 continued:

GLO

Britain, 1831

West South side sec 35

80.00 Ch.

Set post cor. Secs. 34 & 35

Beech 7 N 81° E 24 Lks.

Beech 4 N 49° W 26 Lks.

SURVEY
REMONUMENTATION

APR 29 1880

SECTION

County Survey Records

A. Gardner April 26, 1880

"Stone"

I13 to H13 40.02 Ch. (2641.32')

MDOT Right-of-way Map

Late 1920's

corner not shown

Survey Sketch

Don E. Allen

July 10, 1963

shows distance from S1/8 post of Sec. 34 to the SE corner of Sec. 34 = 1318.56'

LCRC Liber 3, page 178

G.J. Mitchell Dec. 22, 1977

Iron in Mon. Box

(a) 20" Maple WNW 73.60

(b) Telephone Cable Box NNE 58.64

(c) 8" Poplar SE 68.45

Wightman Moored Survey Sketch

Aug. 11, 1987

FD. 1/2" Iron SE Cor Sec. 34 Saug.

FD. Mon. West 8.3'

Shows a distance of 2637.12' from S 1/4 post to I-13

Mitchell Witness Card

same witness's as LCRC Liber 3, Page 178