

MAR 16 1994

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan
(County)

	Located In:	Corner Code #
	Leighton Twp & Dorr Twp	
1. Public Land Survey	T _____ R _____	<u>A-1</u>
	T <u>4N</u> R <u>11W</u>	
	T _____ R _____	
	T <u>4N</u> R <u>12W</u>	<u>M-1</u>
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
 1993 DEC 30 PM 2:42
 FILED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	T4N, R11W					T4N, R12W							
	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert Jonker, in a field survey on October 25, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-1, 1974, Duane Aukron	M-1, MSHD, 1956, Iron in Pavement
3/8" Rod in Concrete	From Road Maps
Iron fence corner N 75° W 46.6'	14" Elm N 36° W 30.75'
NW cor. H/W S 35° W 62.83'	28" Maple N 75° W 47.47'
NE cor. H/W S 35° E 61.56'	30" Maple S 55° W 47.15'

Corner common to 4 townships per G.L.O. maps.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Harrison mon. on C/L N-S pavt. as recorded in Kent Co. as the corner common to 4 townships.


As per the 1974 wit. listed in "A" above.

Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Harrison Monument in Pavement

Fd. N&T SW side P. pole	Az. 303°, 99.0'
Fd. N&T NE side 10" Ash	Az. 314°, 69.48'
Set N&T SE side 10" Ash	Az. 227°, 73.12'
NW cor conc loading dock	Az. 139°, 132.42'
Capped Iron E. 33.02'	
on C/L old roadbed to West	
on field division line to the East	

B-1, East 2629.88'



Signed by Robert J. Jonker Date 12-29-93
 Surveyor's Michigan License No. JONKER LAND SURVEYS 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983