

MAR 16 1994

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
COMMISSION

Allegan
(County)

Located In:
Leighton Twp.

Corner Code #

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>4N</u> R <u>11W</u> | <u>B-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

1993 DEC 30 PM 2:42
Robert J. Jonker
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert Jonker, in a field survey on October 25, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	8	7	6	5	4	3	2	1				
7												
8	9	8	7	6	5	4	3	2	1			
9												
10	10	9	8	7	6	5	4	3	2	1		
11												
12	11	10	9	8	7	6	5	4	3	2	1	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Not set in G.L.O. survey LCRC rec. in L. 2, P. 314, 1974
Donald Ankron, set rebar on twp. line on
old N-S fence line
16" Ash N 60° W 11.87'
"T" Iron East 51.41'
4" Ironwood S 88° W 3.08'


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found N & A (#21272) capped iron on twp. line
51.4' West of the Kent Co. Corner,
other wit. from 1974 are out

Accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with 3/4"x36" standard capped Allegan Co. Monument
Harrison monument East 51.4'
Twp. corner West 2629.88'
NE corner section East 2665.64'
on E-W field division line



Signed by Robert J. Jonker
JONKER LAND SURVEYS
Surveyor's Michigan License No. 21572

Date 12-29-93