

SURVEY &  
REMONUMENTATION

APR 07 1998

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Allegan Co.  
(County)

SECTION

Located in:  
Leighton Twp.

Corner Code #

1. Public Land Survey	T 4N R 11W	B-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.  
*Angela L. Estlin*

98 JAN 21 PM 1:24

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert J. Jonker, in a field survey on October 10, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-13, S. Syn, D.S. 11 May 1826	Ratekin survey, 7-31-79
40.0 Ch. Set qr. sec. post	Found "T" iron
Birch 8 N 52 E 19	W. edge rail East 54'
W. Oak 10 N 59 W 11	Nail - side R.R. crossing sign SE 44.23'
	Gas vent S 40° E 16.3' to fence
	Gas vent N 25° E 25.45' to fence
	PK - side cor. fence post N 10° E 30.58'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found "T" iron on twp. line per Ratekin wit.  
W. edge West rail 54.02' (East)


APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 11-11-97  
COUNTY REP. K.V.O.

Accepted as a careful and faithful perpetuation of the position of the original corner.

Peer group approved Nov. 11, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with standard 24" capped Allegan County monument  
B-1, T3N, R11W, West 9.27'  
W. edge West rail N 90° E 54.02'  
NE cor. ch. link fence post (c/l of post) S 65° W 62.71'  
Allegan Co. Remon & Tag - E. side fence post N 10° E 30.82'  
Allegan Co. Remon & Tag - W. side 5" Elm S 20° W 45.31'



Signed by Robert J. Jonker Date November 10, 1997  
Surveyor's Michigan License No. JONKER LAND SURVEYS, P.C. 21572