

SURVEY &  
REMONUMENTATION

2-1

APR 07 1998

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Allegan Co. Located in: Corner Code #  
(County) Leighton Twp.

1. Public Land Survey T R  
T4N R11W ✓ D-3  
T R  
T R

2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

98 JAN 21 PM 1:25  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert Jonker, in a field survey on 11-28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
1831 - G.L.O. survey Gardner, Apr. 1893  
West corrected bet. Sec. 5 & 8 14 x 8 x 5 Stone  
39.98 Ch. Set qu. sec. post Ash 18 N 28  
Beech 6 S 27 W 18 Walnut 13 SW 37  
Beech 8 N 18 1/2 E 10

Gardner, 1879 - Set stone (over)

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 12-9-97  
COUNTY REP. R.V.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 1/2" pipe in mon box  
All wit. from L.C.R.C. 4-66 - 1990 are out - see over

Accepted as the best available evidence of the position of the corner.

Peer group approved Dec. 9, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with 3/4" x 36" Allegan County monument  
Found PK W. side Fe. cor. post S 33° E 47.45'  
Found PK SE side p. pole S 55° W 50.31'  
Westerly edge stop sign base S 13° E 35.70'  
Westerly edge E. leg of Arrow sign N 1° E 18.75'



Signed by Robert J. Jonker  
Surveyor's Michigan License No. 21572

Date November 29, 1997

Over for Sheet 2

Part "A" Cont'd

D-3 Leighton

LCRC #3-150, 1977, Exxel Eng.  
 Found 3/4" iron checking prev. witnesses

Nail side p. pole SW 48.00'  
 Nail side t. pole SE 41.15'  
 Nail side t. pole NE 34.32'

Ratekin - 1980 Found 1" pipe  
 Dbl.head nail & washer SE side p. pole S 45° W 48.00'  
 Dbl.head nail & washer SW side t. pole S 45° E 41.10'  
 Dbl.head nail & washer SE side t. pole N 30° E 34.34'

1990 - N & A 3/4" Iron  
 same wit. as LCRC #3-150

LCRC #4-66 - Bueche, 1990  
 Found 3/4" iron in mon box  
 per 1st 2 wit. listed above for L.C.R.C. #3-150  
 Took wit.

Nail N. side p. pole SW 48.00' - out 1996  
 Nail NE side t. pole SE 41.15' - out 1996  
 PK SW side 12" Elm out 1996  
 N 40° W 67.47'