

APR 07 1997

SECTION

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan

(County)

Located In:

Leighton Twp.

Corner Code #

- 1. Public Land Survey T 4N R 11W D-13
- T R
- T R
- T R
- 2. Property Controlling in Section S T R
- S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

REGISTER OF DEEDS ALLEGAN COUNTY MICH. *Joyce A. Estlin*

98 JAN 21 PM 1:25

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Robert Jonker, in a field survey on 01-03, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1831 Sylvester Sibley D.S. West on South side Sec.32 40.00 ch. set 1/2 sec. post Birch 7 N22E 22 do 5 N60W 10

W&W LCRC #2-97, 1973, recorded D-1 Wayland Twp. & used as a witness + on stone West 50.00' Also fence corner N70°W 52.39'

APPROVED REMONUMENTATION CORNER P.A. 345 OF 1990 ALLEGAN COUNTY DATE APPROVED 4-8-97 COUNTY REP. K.V.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found stone with "X" on top 50.0' West of D-1, T3N, R11W

Accepted as a careful and faithful perpetuation of the position of the original corner.

Peer group approved Apr. 8, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced stone with std. Allegan County capped monument. Allegan Co. Remon Tag S. side 30" W.Cherry S85°E 15.98' Allegan Co. Remon Tag S. side 30" W.Cherry N90°W 35.32' Allegan Co. Remon Tag E. side 12" Ash S 30°W 65.83' SW corner "L" fence post N 0° 14.94' (on line fence to North also) D-1, Wayland East 50.0'



Signed by Robert J. Jonker Surveyor's Michigan License No. 21572

Date April 04, 1997