

MAR 16 1994

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
COMMISSION
Allegan
(County)

Located in: Corner Code #
Leighton Twp. E-1
T4N R 11W
T R
T R
T R
S T R
S T R
S T R
S T R

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

Robert J. Jonker
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

1993 DEC 30 PM 2:42

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Robert Jonker in a field survey on October 25, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:
G.L.O. jog of 100.98' LCRC rec. in L. 2, P. 395, 1975
per. gov. fieldnotes Set 1/2 iron @ Gov. jog from SW
Cor. sec. 33-5-11 (100.98') - prev. gov. field notes
Nail in S'ly side 14' Walnut NNW 17.36'
Nail in S'ly side 16" Walnut WNW 58.62'
PK in side cor. fce. post SW 29.2'
C/L "X" of gravel East 12'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2" rerod per LCRC rec. in "A" above.
Accepted as the best available evidence of the position of the original corner.

F-1, East 2667.88'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Replaced with 3/4"x36" standard capped Kent Co. monument.

Harrison monument East 100.98'
Nail S'ly side 14" Walnut N 30° W 17.37'
Nail S'ly side 16" Walnut N 70° W 58.58'
PK in side cor. fce. post S 45° W 29.2'
C/L "X" of gravel East 12'
N&T E. side 12" Walnut S 65° W 36.84'
N&T NE side 16" Maple S 40° E 74.85'



Signed by Robert J. Jonker Date 12-29-93
Surveyor's Michigan License No. JONKER LAND SURVEYS 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983