

SURVEY & MONUMENTS

APR 07 1998

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Allegan Co.
(County)

Located in: Corner Code #
Leighton Twp.

1. Public Land Survey	T 4N R 11W	✓ E-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

98 JAN 21 PM 1:25
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.
Sugar & Jonker
FILED
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert Jonker, in a field survey on 12-26, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1831 - G.L.O. survey Stone Gardner - 1893 stake
North between 8 & 9
40.00 set qr. sec. post old notes
Sugar 7 N 11 E 16 corner South 40.0 ch.
Sugar 10 S 30 E 16 mile 79.94 ch.

(over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 5/8" bar per Jonker 1986 listed in "A" above.


APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 12-30-97
COUNTY REP. K.V.O.

Accepted as the best available evidence of the position of the original corner.

Peer group approved Dec. 30, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with standard Allegan County monument 18" below grade
Allegan Co. Remon tag NE side 14" Elm N 30° W 58.05'
Allegan Co. Remon tag E. side 9" Elm N 28° E 144.78'
Allegan Co. Remon tag NW side 4" Elm S 55° W 51.69'
Allegan Co. Remon tag E. side 3" Sass. S 13° W 91.17'



Signed by Robert J. Jonker
Surveyor's Michigan License No. 21572

Date December 23, 1997

FILED 0006 PAGE 141

Over for Sheet 2

Part "A" (Cont'd)

E-4, T4N, R11W
 11-19-85 - Per phone call with Ray Moored at Tri-County Surveys the East $\frac{1}{4}$ Corner is not in. They have a mile distance along the East line of the section of 5264.04' and no deflection at the $\frac{1}{4}$ Corner. They are prorating the mile based on an old mile measurement of 5276.04' by Hugh ~~Medinet~~. *McDougal*

The $S\frac{1}{2}$ of H.M.D. = 2640', prorating 2630'
 The $N\frac{1}{2}$ of H.M.D. = 2636.04', prorating 2630.04' Rob Jonker

Jonker - 1986 Ran E. line Sec. 8-4-11 & set $E\frac{1}{4}$ based on proration above on straight line. Set 5/8"x35" bar in plowed field 18" below grade - took witnesses

Set Spk. S. side 6" Elm S 80° W 55.16'	dead	1996
Set Spk. Ne side 8" Elm N 30° W 58.2'	checked OK	1996
Set Spk. W. side 9" Elm N:10° E 103.75'	out	1996
N-S fence West 10 $\frac{1}{2}$ '	Checked OK	1996
Fence to West South 12'	Checked OK	1996

NE corner of section North 2630.05'
 SE corner of section South 2634.00'