

APR 07 1997

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Allegan</u> (County)	Located In: Leighton Township	Corner Code # ✓ E-13
1. Public Land Survey	T4N R11W	_____
	T_____R_____	_____
	T_____R_____	_____
	T_____R_____	_____
2. Property Controlling in Section	S_____T_____R_____	_____
	S_____T_____R_____	_____
3. Miscellaneous Property in Sec.	S_____T_____R_____	_____
	S_____T_____R_____	_____

98 JAN 21 PM 1:25  
REGISTER OF DEEDS  
ALLEGAN COUNTY MICH.  
FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert Jonker, in a field survey on Jan. 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1831 Sylvester Sibley D.S.  
West on S side Sec. 33, 80.00 ch. set post  
Corner Sec. 31 & 33  
Beech 7 N59E 31  
W. Ash 22 N31W 16

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 4-8-97  
COUNTY REP. K.V.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" solid steel pin 3' S of old E-W fence  
No occupation to N or S  
Found 1' x 1.5' stone 1.3'+- East of E-1, T3N, R11W (G.L.O. jog is 1.32')  
2 links

Accepted as the best available evidence of the position of the original corner.

Peer group approved Apr. 8, 1997.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with standard Allegan County monument.  
SW corner steel fe. post set in conc. N 5°E 15.01'  
Allegan Co. Remon tag & nail N side 20" Walnut S85°E 25.07'  
Allegan Co. Remon tag & nail E side tw. 10" Elm S10°W 11.26'  
Allegan Co. Remon tag & nail N side 10" Ash S85°W 15.78'  
E-1, T3N, R11W, West 1.32'  
Old E-W lying down fence is 3'± N.  
Newer E-W fence is 15' N.

(over)

Signed by Robert J. Jonker  
Robert Jonker  
Surveyor's Michigan License No. 21572

Date 4-4-97



Over for Sheet 2

DEF 0006 corr 143

Part "C" (cont'd)

Replaced with standard Allegan County monument

Set Allegan Co. Tag E. side 10" Tw.Elm S 10° W 11.26'

Set Allegan Co. Tag N. side 10" Ash S 85° W 15.78'