

MAR 16 1994

Allegan County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**COMMISSION**  
Allegan  
(County)

Located in: Leighton Twp. Corner Code #F-1  
1. Public Land Survey T 4N R 11W \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

1993 DEC 30 PM 2:42  
Register of Deeds Stamp & File Number  
Jasper A. Lehto  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICHIGAN

FILED

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert Jonker, in a field survey on October 25, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Not set in G.L.O. survey LCRC rec. in L. 1, P. 90 LCRC rec. in L. 2, P. 112  
Co. Road Com. 1965: Ratekin, 1971-- 1 1/2" Pipe  
C.P. NNE 21.8' P. pole N 10° E 21.8' Paul VanKooten, 1973  
USGS BM ENE 62.0' 18" Walnut S 20° W 64.5' Found "T" Iron  
15" W. Cherry SE 72.15' 8" Walnut South 41.1' PK P.pole NNE 22.21'  
18" Walnut SSW 64.5' C/L gravel rd S 5' Spk 24" Wal. SW 40.79'  
Co. Road Com., no date Spk 26" Wal. SSW 65.8'  
88.46' Rt of P.I. #4 of survey Spk 24" Map. ENE 69.22'


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found "T" Iron 83.2' West of Kent Co. Corner & 0.04' N of Twp. line.  
1965 wit. 1971 wit. 1973 wit.  
C.P. NNE 21.8' P. pole N 10° E 21.8' "T" Iron  
C/L Walnut South 41.1'± P. pole NNE 22.21'  
Walnut SW 40.79'

Accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4"x36" standard capped Allegan Co. Mon. on Twp. line  
Fd. PK nail, W. side P. pole Az. 12°, 22.19'  
Harrison mon. East 83.2'  
Set N&T S. side Tw. 12" Maple Az. 290°, 55.88'  
Set N&T E. side 9" Walnut Az. 186°, 59.25'  
Set N&T NW side 28" Walnut Ax. 218°, 41.03'  
C/L E-W gravel road, South 6'±  
on C/L extended from South  
on line 3 trees to South E-1, West 2667.88'  
G-1, East 2668.53'



Signed by Robert J. Jonker Date 12-29-93  
JONKER LAND SURVEYS  
Surveyor's Michigan License No. 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983