

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan
(County)

Located In: _____

Corner Code ~~F-7~~

- | | | | | |
|------------------------------------|---|-------|-----|------------------|
| | | 4N | 11W | F-7 (S¼ cor. 16) |
| 1. Public Land Survey | T | _____ | R | _____ |
| | T | _____ | R | _____ |
| | T | _____ | R | _____ |
| | T | _____ | R | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ |
| | S | _____ | T | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ |
| | S | _____ | T | _____ |

~~Leighton Twp.~~

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

97 JAN 22 PM 1:25
 FILED
 REGISTER OF DEEDS
 ALLEGAN COUNTY
 Michigan State Surveyors

Register of Deeds Stamp & File Number

I, Steven Koerber, in a field survey on October 3, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|----------------------------------|------------------------------|
| F-7 GLO Sylvester Sibley DS 1831 | 1. Old County Surveyor Notes |
| Maple 8 N39W 9 | Stone |
| Maple 8 S21E 34 | Nov. 15, 1870 |
| | E. Strong DS |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7 Found square head nail on C/L 144th & on tree row to North
Fnd. spike in S. sdc. 12" Apple N75°E 75.20'

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.
Peer Group approval November 12, 1996.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 11-12-96
COUNTY REP. Paul J. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-7 Replaced square head nail with Allegan Co. Mon. (3/4" x 24" Iron Rod with Remonumentation cap)
Set 3/4" x 24" Allegan Co. Remon. Iron Rod and Remon. witness cap N50°E 67.84'
Set 3/4" x 24" Allegan Co. Remon. Iron Rod and Remon. witness cap N30°W 72.61'
Set 3/4" x 24" Allegan Co. Remon. Iron Rod and Remon. witness cap S55°W 84.77'
Set 3/4" x 24" Allegan Co. Remon. Iron Rod and Remon. witness cap S5°W 60.16'
E-7, T4N, R11W 2653.69'
G-7, T4N, R11W 2656.64'

Signed by [Signature] Date 12-10-1996

Surveyor's Michigan License No. 39085



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS, JAN. 29, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983