

APR 07 1997

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan</u> (County)	Located In: Leighton Township	Corner Code # F-13
1. Public Land Survey	T4N R 11W	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds
ALLEGAN COUNTY, MICH.

98 JAN 21 PM 1:25

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert Jonker, in a field survey on Jan. 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1831 Sylvester Sibley D.S. LCRC #3-328, MVK #8618, 1982
West on South side Sec. 33 Part A - found 1" solid rod on line fe. & tree
40.00 ch. set qtr. post row to N & on fe: line to the W, piled stones
Beech 17 N40E 15 around iron.
Beech 7 N50W 29 Took witnesses of:
Sq. spk N side 12" Maple W 21.45' - ck. ok 1997
Sq. spk W side 8" Maple N 12.11' - ck. ok 1997
Sq. spk SE side 8" W. Cherry SW 24.45'
Old wit. in face 14" W. Ch. N 16.4' -ck. ok '97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.


Found 1" solid steel pin by wit. listed in "A" above for LCRC 3-328

Accepted as the best available evidence of the position of the original corner.

Peer group approved Apr. 8, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Replaced with 3/4" x 36" std. capped Allegan Co. Mon.
Wayland corner West 6.55'
Allegan County Remon tag & nail in NE side 9" Maple N32°W 33.21'
Allegan County Remon tag & nail W side 10" Maple N11°E 12.08'
Allegan County Remon tag & nail in N side 19" Maple N83°W 21.60'
Allegan County Remon tag & nail in SE side P.Pole N65°E 40.74'



APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 4-8-97
COUNTY REP. K.V.O.

Signed by Robert J. Jonker
Surveyor's Michigan License No. Robert Jonker 21572

Date 4-4-97