

MAR 16 1994

For corners in

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COM Allegan County

Located in: Leighton Twp.

Corner Code ##

- 1. Public Land Survey T 4N R 11W G-1
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Robert A. Jonker
REGISTER OF DEEDS
ALLEGAN COUNTY MICHIGAN

1993 DEC 30 PM 2:42

FILED

Register of Deeds Stamp & File Number

I, Robert Jonker, in a field survey on October 25, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5						3	2				
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Jog per G.L.O. field notes 64.68'

No info. available from road comm. or Co. Surveyors office.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found boat spike in mon. box 0.35' North of twp. line

Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4"x24" capped standard Allegan Co. mon. on twp. line

Set N&T on top cor. fce. post Az. 145°, 53.93'

Set N&T on W. side 24" Walnut Az. 108°, 92.6'


Set N&T on side U. pole Az. 50°, 84.6'

Harrison mon. East 64.68'

on C/L to E-W, South

F-1, West 2668.53'

H-1, East 2654.27'



Signed by Robert J. Jonker Date 12-29-93

Surveyor's Michigan License No. JONKER LAND SURVEYS 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 004 PAGE 301