

**SURVEY &
REMONUMENTATION**

APR 07 1998

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

<u>Allegan</u> (County)	Located in:	Corner Code #
	Leighton Township	
1. Public Land Survey	T 4N R 11W	G-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

98 JAN 21 PM 1:25
FILED
Robert J. Jonker
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert Jonker, in a field survey on Jan. 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1831 Sylvester Sibley D.S.
West on S side 34, 80 ch. set post Sec. 33&34
Pine 5 N75E 2, Pine 8 N82½W 28
Wayland Twp. corner is 4.62' West
Ratekin 1973 - F-13, G-13 2639.7'

MVK - 1982, 1½" iron pipe
Sq. spk. SW side 12" Maple NW 20.85'
Sq. spk. Nly side 10" Maple 17.3'
Sq. spk. NW side 8" Maple NE 4.9'
Sq. spk. Wly 12" tw. Maple SSW 25.84'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 1½" iron pipe by wit. listed in "A" above - from MVK 1982

Accepted as the best available evidence of the position of the original corner.

Peer group approved Apr. 8, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 24" Std. Allegan County Remon. pin & cap inside of existing pipe.
Found sq. spk. N side 10" Maple 17.36'
Found sq. spk. W side 20" Tw. Maple S20°W 25.89'
Found sq. spk. SW side 12" Maple N35°W 20.92'
Set Remon tag in W side 10" Maple N65°E 4.85'
There is a N-S fence 0.5' East of corner
Fence to West is 1' North of corner



APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 4-8-97
COUNTY REP. K.V.C.

Signed by Robert J. Jonker
Surveyor's Michigan License No. Robert Jonker 21572

Date 4-4-97