

MAILED
COMMISSION
For corners in

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Allegan (County) Located In: Corner Code #
Leighton Twp.

1. Public Land Survey T 4N R 11W H-1
T R
T R
T R

2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

1993 DEC 30 PM 2:42
Register of Deeds Stamp & File Number
FILED
PROFESSOR OF DEEDS
AND RECORDS
ALLEGAN COUNTY, MICHIGAN
Robert J. Jonker

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert Jonker, in a field survey on October 25, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Not set in original G.L.O. survey.
No wit. available from records or Co. Surveyors.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1" Iron pipe in mon. box 0.15' N of Twp. line.
Set corner on Twp. line.

Accepted as the best available evidence of the position of the corner.

G-1, West 2654.27'
I-1, East 2654.36'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 3/4"x36" capped standard Allegan Co. monument in mon. box.

- Harrison monument East 58.97'
- Fd. N&T W. side 18" Ash Az. 206°, 22.07'
- Fd. N&T NE side 10" Ash Az. 143°, 23.9'
- Fd. N&T W. side U. pole Az. 45°, 85.80'
- Set N&T W. side 50" Maple Az. 181°, 96.60'
- R/W iron Az. 185°, 33.35'
- C/L E-W pavement is 2' North on brush and tree row to South



Signed by Robert J. Jonker Date 12-29-93
Surveyor's Michigan License No. JONKER LAND SURVEYS 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 22, 1971
REVISED MAY 14, 1975
REVISED JAN., 1982