

**SURVEY &
REMONUMENTATION**

APR 07 1998

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

<u>Allegan</u> (County)	Located In: Leighton Township	Corner Code#
1. Public Land Survey	T 4N R 11W	✓ H-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

98 JAN 21 PM 1:25
REGISTER OF DEEDS
ALLEGAN COUNTY
Joyce A. Lattin
FILED
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert Jonker, in a field survey on Jan. 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1831 Sylvester Sibley D.S.
West on S side Sec. 34, 40.00 ch., set gr. Sec. post
Beech 7 N49E 37
Beech 7 N65W 25
July 13, 1982, MVK, L.C.R.C. 3-373
Fd. 2 flat stones set on edge by fence corner to W & N.
PK SW side cor. fe. post WNW 1.96'
Sq. spk E side 14" Hickory NNE 4.75'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found MVK capped iron by wit. listed in A above for L.C.R.C. 3-373.

Accepted as the best available evidence of the position of the original corner.

Peer group approved Apr. 8, 1997.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Replaced with 3/4" x 36" std. capped Allegan Co. Mon.
Found pk nail SW side fence corner post N50°W 1.96'
Found sq. spk E side 15" Hickory N30°E 4.75'
Set Allegan Co. Remon tag & nail E side 15" N30°E 4.83'
Set Allegan Co. Remon tag & nail S side N75°W 17.79'
Set Allegan Co. Remon tag & nail SE side 10" S30°W 18.35'
Fence to West is 1 1/2' North
Fence to South is 13'± West
H-1, Wayland - West 12.82'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 4-8-97
COUNTY REP. K.V.O.
Date 4-4-97

Signed by Robert J. Jonker
Surveyor's Michigan License No. 21572

LIBR 0006 PAGE 147