

MAR 1 6 1993

Allegan County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION  
For corners in

Allegan (County)

Located in: Leighton Twp. Corner Code #

1. Public Land Survey	T <u>4N</u> R <u>11W</u>	<u>T-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

*Robert J. Jonker*  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICHIGAN

1993 DEC 30 PM 2:42

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1. Robert Jonker, in a field survey on October 25, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. jog 24 links, 15.84'

Ratekin, 1969, Fd. "T" Iron  
 St. sign NE 40.55'  
 St. sign NW 28.3'  
 P. pole SW 59.95'

Kirk VanOrder, 1991  
 "T" Iron 53.02' West  
 of Kent Co. corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 1" iron in mon. box - raised over "T" iron, on twp. line

Accepted as the best available evidence of the position of the original corner.

H-1, West 2654.36'  
 J-1, East 2683.49'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Replaced with 3/4"x36" standard capped Allegan Co. monument.

Set N&T N'yly side 16" Maple Az. 294°, 83.04'  
 Set N&T W'yly side U. pole Az. 63°, 103.17'  
 Set N&T NW side 12" Maple Az. 225°, 91.0'  
 R/W iron in pavement Az. 184°, 33'  
 Harrison monument East 53.02'  
 C/L E-W pavement South 4½'  
 C/L gravel road to South 17½' West±



Signed by Robert J. Jonker Date 12-29-93  
 JONKER LAND SURVEYS  
 Surveyor's Michigan License No. 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1982