

SURVEY & REMONUMENTATION

9-2

APR 07 1999

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan</u> (County)	Located In: Leighton Township	Corner Code # I-13
1. Public Land Survey	T 4N R 11W	✓ I-13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTER OF DEEDS
 ALLEGAN COUNTY MI.
 98 JAN 21 PM 1:25
 FILED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert Jonker, in a field survey on Jan. 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1831 Sylvester Sibley D.S.
 West on S side Sec. 35, 80.0 ch. set post
 Corner Sections 34 & 35
 Sycamore 5 N79E 27
 Sycamore 20 N62W 34

LCRC 3-410 Jonker 1985
 Set corner per gov. jog of 47 links (31.02') East of the Wayland corner per info. received from Ratekin.
 Set capped rerod
 1" st. pin West 31.02'
 C/L top steel fe. post S40°W 83.25'
 PK nail N side fe. post West 5.98'
 Iron 3' W of C/L pvt. W 278.5' m/l

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.


Found Jonker capped iron per wit. listed in "A" above for LCRC 3-410.

Accepted as the best available evidence of the position of the original corner.

Peer group approved Apr. 8, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Replaced with 3/4" x 36" capped Allegan Co. Mon. in field
 1" solid iron West 31.02' (Wayland corner).
 Allegan County remon tag & nail S side fence corner post N75°W 6.62'
 Allegan County remon tag & nail SW side fence corner post N35°W 13.63'
 Allegan County remon tag & nail S side 10" quad tree N90°E 65.0'
 E-W line fe. 2' N



APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 4-8-97
 COUNTY REP. R.V.O.

Signed by Robert J. Jonker
 Surveyor's Michigan License No. Robert Jonker 21572

Date 4-4-97

Over for Sheet 2

11872 0006 PAGE 148

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983
 REVISED OCT. 1985

Part "A" con't.

1986 Kirk Van Order
Fd. Jonker capped iron #21572
E. face 19" Hick. W 27.91'
C/L st. fe. post SW 83.1'
NE cor. house fndn. WSW 120.55'
Capped iron W 278.54'

1990 Exxel Eng. iron
1" iron W 31.02'
C/L steel fe. post for pool SW 83.25'
Iron W 278.5'