

NR 16 1993

Allegan County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

CONNECTION  
For corners in  
Allegan

	Located in:	Corner Code #
	Leighton Twp.	
1. Public Land Survey	T <u>4N</u> R <u>11W</u>	<u>J-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1993 DEC 30 PM 2:42  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY MICHIGAN  
 J. C. [Signature]

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert Jonker, in a field survey on October 25, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
Not set in G.L.O. survey

- 1969, Ratekin, Set 1" Iron
- 24" Maple WSW 82.7'
- NE cor. barn SSW 96.85'
- 13" Oak SSW 30.0'
- 16" Oak NNE 25.5'
- 12" Walnut NE 48.65'


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found 1/2" capped rerod (#?) in mon. box 0.07' South of Twp. line
- 1969 wit.
- Maple WSW 82.7'
- Cor. barn SSW 96.85'
- Oak NNE 25.5'

Accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 3/4"x24" standard capped Allegan Co. Monument on Twp. line
- Set N&T on W. side U. pole Az. 21°, 58.44'
- Set N&T on S. side 36" Maple Az. 253°, 83.96'
- NE cor conc fndn to barn Az. 200°, 96.90'
- Fd. C.P. Co. tag
- E. side 27" Oak Az. 22°, 26.3'
- Harrison Monument East 16.67'
- I-1, West 2683.49'
- K-1, East 2683.90'



Signed by Robert J. Jonker Date 12-27-93  
 JONKER LAND SURVEYS  
 Surveyor's Michigan License No. 21572

LIBER 001 PAGE 304