

REMONUMENTATION

MAR 16 1993

Allegan County Remonumentation
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan
 (County)

Located In:
Leighton Twp.

Corner Code #/

1. Public Land Survey	T <u>4N</u> R <u>11W</u>	<u>K-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
Robert J. Jonker

1993 DEC 30 PM 2:42

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

I, Robert Jonker, in a field survey on October 25, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-1, Rec. LCRC in L. 3, P. 180, 3/4" Rod, 1976
 P. pole N 47° W 94.62'
 P. pole N 14° E 63.6' Ratekin, 1969, Set 1" Iron
 T. pole S 38° E 42.16' USGS BM SSW 70.2'
 T. pole SE 41.85'
 Rec. in LCRC in L. 3, P. 360, 1983 St. sign SE 39.85'
 Doug Bonnema, Fd. Harrison Mon. P. pole NNE 63.1'
 Capped Iron W 12.76' N&T P. pole ENE 169.84'
 N&T P. pole NW 94.69' N&T 2" Ash SE 100.83'
 N&T P. pole NNE 63.34'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found C.I. mon. 0.1' North of Twp. line & 14.30' East of Kent Co. corner by wit. listed above for LCRC., 1983

Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Kent Co. Mon. West 14.30'
 N&T E'ly side P. pole N 47° W 94.78'
 N&T E'ly side P. pole N 14° E 63.38'
 PK in E. side sign post S 25° W 70.56'
 N&T S'ly side P. pole N 70° E 169.89'

J-1, West 2683.90'
 L-1, East 2636.21'



Signed by Robert J. Jonker Date 12-29-93
 Surveyor's Michigan License No. JONKER LAND SURVEYS 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983