

Allegan County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan (County)	Located In:	Corner Code #
	4N 11W	K-8 (E 1/4 cor. 23)
1. Public Land Survey	T _____ R _____	Leighton Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

97 JAN 22 PM 1:25
 FILED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Steven Koerber, in a field survey on October 3, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	10	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-8 GLO Sylvester Sibley DS 1831 W. Oak 7N33E 66 DO 35 S34E 43 (Additional info. on back of sheet)	1. Old Notes 3/4" pipe over 1" Flat Bar (1966) 10" Walnut ESE 88.7' St. sign SE 31.8" T. Pole NW 47.0' 18" Maple WNW 71.2' 2651.49 to NE cor 23 2655.85 to center 24 2649.03 to SE cor. 23	2. October 22, 1973 L.C.R.C., L. 2, PG. 146 Don Ratekin Found 3/4" pipe over 1" flat bar (1966) 12" Walnut S60°E 88.7' St. sign S40°E 31.8" 20" Maple N55°W 71.2'
---	--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


K-8 Found 3/4" Iron Pipe
 (30") 20" Maple N55°W 71.2' (M= 72.0 to spike in S. side)
 (24") 12" Walnut S60°E 88.7' (M= 89.3' to nail in N. side)

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.
 Peer Group approval November 12, 1996

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 11-12-96
 COUNTY REP. Neil J. Tomlinson

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 Replaced 3/4" Iron Pipe with Allegan Co. Mon. (3/4" x 24" Iron Rod with Remonumentation cap)
 Nail & Allegan Co. Remon. Tag in N. side 24" Maple N50°W 117.89'
 Nail & Allegan Co. Remon. Tag in S. side 12" Maple N60°W 95.46'
 Nail & Allegan Co. Remon. Tag in SW corner old brick school bldg. (Standard School) N40°W 170.38'
 Nail & Allegan Co. Remon. Tag in W. side 8" Walnut S40°E 36.92'
 K-7, T4N, R11W 2651.47'
 L-9, T4N, R11W 2659.70'



Signed by Steven C. Koerber Date 12-10-1996
 Surveyor's Michigan License No. 39085

0005 PAGE 446

K-8, T4N, R11W
3. March 30, 1973
PA 132 drawing
Don Ratekin
same wits. as No. 2 above

