

Allegan County Remonumentation
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Robert J. Jonker
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN

1993 DEC 30 PM 2:42

FILED

MAR 16 1994
 COMMUNICATIONS

For corners in
Allegan
 (County)

	Located In:	Corner Code #
	Leighton Twp.	
1. Public Land Survey	T <u>4N</u> R <u>11W</u>	<u>L-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	15	14	13	12	11	10	9	8	7	6	5	4	3
7													
8	19	18	17	16	15	14	13	12	11	10	9	8	7
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

I, Robert Jonker, in a field survey on October 25, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

LCRC rec. in L. 3, P. 100, Pointed Stone, glass & charred wood, 1976
 20" Basswood S 29° W 18.0'
 6" Oak N 10° E 31.8'
 30" Oak N 79° W 45.72'
 on S. edge gravel 9'± S. of C/L as traveled
 Not set in G.L.O. survey.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" capped rerod 0.39' S. of Twp. line, on brush row to South by all wit. listed on LCRC in "A" above.

Accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with 3/4"x36" standard capped Allegan Co. mon. on twp. line
 Kent Co. Mon. West 5.95'
 Fd. N&T S. side 30" Oak Az. 312°, 45.71'
 Fd. N&T E. side P. pole Az. 194°, 33.02'
 Fd. N&T SW side 16" Basswood Az. 263°, 59.97'
 SW angle point of bottom of
 SW leg of steel tower Az. 42°, 243.84'
 K-1, West 2636.21'
 M-1, East 2643.14'



Signed by Robert J. Jonker Date 12-29-93
 JONKER LAND SURVEYS
 Surveyor's Michigan License No. 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983