

Allegan County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Allegan  
(County)

Located in: 4N 11W  
Corner Code: L-7 (N¼ cor. 24)  
~~Leighton-Twp.~~

1. Public Land Survey T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
2. Property Controlling in Section S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_  
3. Miscellaneous Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

97 JAN 22 PM 1:25  
REGISTERED  
ALLEGAN COUNTY  
REGISTER OF DEEDS STAMP & FILE NUMBER

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Steven Koerber, in a field survey on October 3, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
L-7 GLO Sylvester Sibley DS 1831  
Bocch 5 N63W 12  
DO 10 S51E 28

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
L-7 Nothing found at corner location.  
Set corner ½ way and on line between K-7 and M-7.  
  
This corner is accepted as a careful and faithful reestablishment of the position of the original corner.  
Peer Group approval November 26, 1996.

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 11-26-96  
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
L-7 Set Allegan Co. Mon. ( 3/4" x 24" Iron Rod with Remonumentation cap)  
Nail & Allegan Co. Remon. Tag in NE side 10" Apple S30°E 1.55'  
Nail & Allegan Co. Remon. Tag in W. side 8" Elm stem on Elm clump S10°W 11.81'  
Nail & Allegan Co. Remon. Tag in W. side 10" Hickory N0°E 7.60'  
Nail & Allegan Co. Remon. Tag in E. side 4" Hickory N10°E 10.72'  
N-S fence line 2.5' West  
L-8, T4N, R11W 2645.17'  
K-7, T4N, R11W 2654.82'  
M-7, T4N, R11W 2654.81'



Signed by [Signature] Date 12-10-1996  
Surveyor's Michigan License No. 39085

USE: 0005 PAGE 448

FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS, JAN. 26, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1993