

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan (County)	Located in:	Corner Code #
	4N 11W	L-8 (Center 1/4 cor. 24)
1. Public Land Survey	T ___ R ___	Leighton Twp.
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 97 JAN 22 PM 1:25
 FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	16	15	14	13	12	11	10	9	8	7	6	5	4
7													
8	19	18	17	16	15	14	13	12	11	10	9	8	7
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

I, Steven Koerber, in a field survey on October 3, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-8 No corner set by GLO	1. Old Notes 1/2" iron over 1" iron 18" deep (1966) Rail fnc. post N 27.01' 16" Cherry SE 72.5' Chiseled "T" in rock SSW 29.4' T. Pole SW 44.15' 2655.85 to W 1/4 24 2645.65 to S 1/4 cor 24	2. October 22, 1973 L.C.R.C., L. 2, PG. 146 Don Ratekin Found 1/2" iron (1966) Rail fnc. post N 27.01' 18" Cherry S55°E 72.5' Chiseled "T" in flat rock S10°W 29.4'
--------------------------	--	--

(Additional info. on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-8 Found 1/2" capped iron (R.E.M.)
 Rail fnc. post N 27.01'
 (24") 18" Cherry S55°E 72.5' (M± to face)

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 11-26-96
 COUNTY REP. [Signature]

This corner was established using improper procedures and is not utilized in this survey.

New corner position set at the intersection of 1/4 section lines. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-8 Set Allegan Co. Mon. (3/4" x 24" Iron Rod with Remonumentation cap)
 Nail & Allegan Co. Remon. Tag in SE side P. pole N60°E 98.09'
 Nail & Allegan Co. Remon. Tag in W. side 8" Elm S20°E 57.00'
 Nail & Allegan Co. Remon. Tag in W. side 8" Walnut S0°E 63.52'
 Set 3/4" x 24" Allegan Co. Remon. Iron Rod and Remon. witness cap N35°W 66.99'

L-7, T4N, R11W	2645.17'	N00°02'06"W
K-8, T4N, R11W	2659.70'	S89°51'17"W
L-9, T4N, R11W	2644.17'	S00°02'06"E
M-8, T4N, R11W	2653.15'	N89°51'17"E



Signed by [Signature] Date 12-10-1996

Surveyor's Michigan License No. 39085

FILED 0005 PAGE 449

L-8, T4N, R11W

3. March 30, 1973
PA 132 drawing
Don Ratekin
same wits. as No. 2 above

4. Wightman-Moored notes 1989
Found 1" bent iron 18" deep
placed 1/2" capped pipe over
1" iron