

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Alleghan
(County)

Located In: 4N 11W
Corner Code L-9 (South 1/4 cor. 2+)
Leighton Twp.

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

S T R
S T R
S T R
S T R

97 JAN 22 PM 1:25
REGISTERED
ALLEGHAN COUNTY
FILED

Register of Deeds Stamp & File Number

- 4. Lot No: _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	5	5	5	5	5	5	5	5	5	5
3	6	6	6	6	6	6	6	6	6	6	6	6
4	7	7	7	7	7	7	7	7	7	7	7	7
5	8	8	8	8	8	8	8	8	8	8	8	8
6	9	9	9	9	9	9	9	9	9	9	9	9
7	10	10	10	10	10	10	10	10	10	10	10	10
8	11	11	11	11	11	11	11	11	11	11	11	11
9	12	12	12	12	12	12	12	12	12	12	12	12
10	13	13	13	13	13	13	13	13	13	13	13	13
11	14	14	14	14	14	14	14	14	14	14	14	14
12	15	15	15	15	15	15	15	15	15	15	15	15
13	16	16	16	16	16	16	16	16	16	16	16	16

I, Steven Koerber, in a field survey on October 3, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-9 GLO Sylvester Sibley DS 1831
W. Oak 8 S59E 10
Do 7 N24W 14

1. Wightman-Moored Notes
Jonker cap in 1" pipe
Nail in SE side W. Pole N40°E 86.59'
N. face 4" steel post S2°E 34.40'
NW face 4" Steel post S40°E 38.92'
in line with fence to North
2645.65 to Center 1/4 cor 24
2664.38 to SW cor. 24

2. Feb. 14, 1990
L.C.R.C., L. 4, PG. 63
James Miller
Found 1/2" iron with cap
North 33.77' PK nail in E. face of Anchor post
N55°E 86.61' PK nail in P. pole
S35°W 16.78' Nail/Washer in 9" Oak
South 34.5' 4 1/2" Diam. steel post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9 Found Jonker cap in 1"x30" pipe
N55°E 86.61' PK nail in P. pole
South 34.5' 4 1/2" Diam. steel post
North 33.77' PK nail in E. face of Anchor post

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.
Peer Group approval November 12, 1996.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGHAN COUNTY
DATE APPROVED 11-12-96
COUNTY REP. Paul E. Hanlon

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 Replaced 1" Iron Pipe with Alleghan Co. Mon. (3/4" x 24" Iron Rod with Remonumentation cap)
Nail & Alleghan Co. Remon. Tag in NE side wood P. pole (westerly pole of twin pole set) S25°E 114.00'
Nail & Alleghan Co. Remon. Tag in NW side wood P. pole (westerly pole of twin pole set) N50°E 86.30'
Nail & Alleghan Co. Remon. Tag in SE side wood P. pole (easterly pole of twin pole set) N55°E 99.23'
Nail & Alleghan Co. Remon. Tag in W. side 4"x4" wood post S2°E 30.74'
L-8. T4N, R11W 2644.17'
M-9, T4N, R11W 2651.56'



Signed by [Signature]
Surveyor's Michigan License No. 39085

Date 12-10-1996

USER 0005 PAGE 451

L-9, T4N, R11W

3. Exxel Eng. April 1991
used iron with Jonker cap-
did not witness.