

**SURVEY &
REMONUMENTATION**

APR 07 1998

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **SECTION**

<u>Allegan</u> (County)	Located In: Leighton Township	Corner Code #
1. Public Land Survey	T4N R11W	' L-13
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

**REGISTER OF DEEDS
ALLEGAN COUNTY MICH.**
Robert J. Jonker
 98 JAN 21 PM 1:26
FILED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert Jonker, in a field survey on Apr. 4, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 4-8-97
 COUNTY REP. K.V.O.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1831 Sylvester Sibley D.S.
 West on S side Sec. 36, 40.00 ch. set qtr Sec. post
 Hickory 8 N69E 10
 W Oak 22 N64W 41

Ratekin map - 1/2 mile to West 2677.12'
 - 1/2 mile to East 2653.70'

Co. Road. Comm (old) prior to 1979
 5 1/2 post - iron pipe
 12" Boxelder NE 47.7'
 12" Oak SE 34.6'
 18" Oak SW 53.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" solid pin in mon. box on C/L E-W pavement & fence line to North checks per road comm. wit. of 18" Oak SW 53', rest of wit. are out.

Accepted as a careful and faithful perpetuation of the position of the original corner.

Peer group approved Apr. 8, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with standard Allegan County monument.
 PK nail on NE side P.Pole S45°E 78.78'
 Set spk. E side 14" Oak S25°W 40.26'
 Set spk. W side 32" Oak S52°W 53.66'
 Set PK SW P.Pole N52°W 61.60'
 Jonker capped iron West 20.65 (N 1/4 Sec. 1, Wayland Twp.)



Signed by *Robert J. Jonker*
 Surveyor's Michigan License No. Robert Jonker 21572

Date 4-7-97