

Allegan County Remonumentation  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

REMOVED  
 MAR 16 1994  
 For corners in  
 Allegan  
 (County)  
 COMMISSIONER

1993 DEC 30 PM 2:42  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY MICHIGAN  
 Robert J. Jonker

FILED

Located in: Leighton Twp. Corner Code # M-1

1. Public Land Survey	T <u>4N</u> R <u>11W</u>	<u>M-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert Jonker, in a field survey on October 25, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 LCRC rec. in L. 3, P. 100, Perry McPherson, for C.P. Co., R.R. spike, 1976  
 P. pole N 14° E 114.24'  
 P. pole S 42° E 61.74'  
 Guard post S 41° W 29.18'  
 USGS Mon. S 43° E 47.9'  
 on C/L to S.±, & 9' S.± of E-W C/L  
 1½'± W. of C/L to North

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 4" cast iron mon. set by Kent Co. Remonumentation program.  
 Witnesses check per LCRC listed in "A" above.

Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 4" Cast Iron Monument 3' W. of C/L to N & S, & 7' S. of C/L to E-W  
 N&T E. side Guy pole Az. 348°, 78.81'  
 N&T W. side U. pole Az. 20°, 114.19'  
 N&T W. side U. pole Az. 143°, 61.55'  
 C/L top USGS BM, stamped elev. 797 feet Az. 142°, 47.54'

L-1, West 2643.14'



Signed by Robert J. Jonker Date 12-29-93  
 JONKER LAND SURVEYS  
 Surveyor's Michigan License No. 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983